


architecture california the journal of the american institute of architects california council

aiacc design awards issue

05.3



drawing for architecture

Drawing Berlage's Exchange

Ain, Hartmann, Kulper, Lautner, Neutra


And The Winners Are . . .

Maybeck Award: Rob Wellington Quigley, FAIA | 25-Year Award: Art Center College of Design, Craig Ellwood Associates

Firm of the Year Award: Morphosis | Firm of the Year Award: RATCLIFF

Lifetime Achievement Award: John Field, FAIA

TURN YOUR IDEAS INTO REALITY



WOW!!!! We said the same thing, those aluminum windows are SPECTACULAR!





05.3

aiacc design awards issue

37 & Lauren Weiss Bricker, Ph.D.

drawn out

Content

Alexander Ortenberg, PhD, quest editor/curator

Introduction 10 ☆ Alexander Ortenberg

Let Me Illustrate 12 A Tulay Atak

Representing Beyond the Surface 16 ☆ Perry Kulper

Gregory Ain: Drawings against Photographs 20 ☆ Anthony Denzer

John Lautner: 26 🖈 Jon Yoder

Diagramming Vision in Los Angeles

The Late Travel Sketches of

Sugar Daddy: Drawing Berlage's Exchange 30 ☆ Wendy Kohn

bugai Daddy. Diawing Deriage's Exchange 30 % wendy Konn

Richard J. Neutra: Seeing His World

Color Plates 41

AIACC 2005 AWARDS

49

Maybeck Award: 52

Rob Wellington Quigley, FAIA

25-Year Award: 54

Art Center College of Design

Firm of the Year Award: 56

Morphosis

Firm of the Year Award: 58

RATCLIFF

Lifetime Achievement 60

Award: John Field, FAIA

Design Awards 62

Savings By Design Awards 86

Comment3Contributors9Credits115Coda116

arcca

05.3

Editor

Tim Culvahouse, AIA

Culvahouse Consulting Group, Inc.

Editorial Board

Paul Halajian, AIA Chair John Leighton Chase, AIA Peter Dodge, FAIA

Wendy Kohn

Kris Miller-Fisher, AIA Eric Naslund, FAIA

Pierluigi Serraino, Assoc. AIA

Kelly Walker

Thomas M. Anglewicz, AIA

Design

Bob Aufuldish Ragina Johnson Aufuldish & Warinner

Production

Greg Delviscio Lorraine Sacca

Publisher

Roylin Downs California Regional Publisher

McGraw-Hill Construction

AIACC

Lori Reed, Director of Marketing

and Communications

arcCA is dedicated to providing a forum for the exchange of ideas among members, other architects and related disciplines on issues affecting California architecture. arcCA is published quarterly and distributed to AIACC members as part of their membership dues. In addition, single copies and subscriptions are available at the following rates:

> Single copies: \$6 AIA members; \$9 non-members. Subscriptions (four issues per year): \$24 AIA members; \$15 students; \$34 non-members, U.S.; \$38 Canada; \$42 foreign.

Subscriptions: arcCA, c/o AIACC, 1303 J Street, Suite 200, Sacramento, CA 95814, www.aiacc.org

Advertising: 877.887.7175.

Inquiries and submissions: Tim Culvahouse, Editor: tim@culvahouse.com; Culvahouse Consulting Group, Inc., 2919 Florence Street, Berkeley, CA 94705; 415.309.2085; fax 510.665.4007. Bob Aufuldish, Aufuldish & Warinner: bob@aufwar.com.

Copyright and reprinting: © 2005 by AIACC. All rights reserved. Reproduction in whole or in part without permission is prohibited. Permission is granted through the Copyright Clearance Center (CCC), 222 Rosewood Drive, Danvers, MA 01923. arcCA is a trademark of AIACC.

arcCA (ISSN 0738-1132) is published by The McGraw-Hill Companies on behalf of The American Institute of Architects, California Council. McGraw-Hill and AIACC are not responsible for statements or opinions expressed in arcCA, nor do such statements or opinions necessarily express the views of AIACC or its committees. Contributors are responsible for credits and copyright permissions. Third class postage paid at Shepherdsville, Kentucky. Printed on recycled paper by Publishers Press.

McGraw Hill Architectural Record ENR Regional Publications

Dodge

AIACC

The American Institute of Architects. California Council 1303 J Street, Suite 200 Sacramento, CA 95814 916.448.9082 ph 916.442.5346 fax www.aiacc.org

2005 Executive Committee

President

Stephan Castellanos, FAIA

First Vice President/President-elect

John Melcher AIA Treasurer

Jeffrey J. Emrick, PE AIA

Secretary

Roseanne McNulty, AIA Vice President of

Regulation and Practice

Jeffrey T. Gill, AIA

Vice President of Legislative Affairs

Pamela M. Touschner, AIA Vice President of

Communications/Public Affairs Thomas M. Anglewicz, AIA

Executive Vice President Paul W. Welch, Jr., Hon, AIA

AEP Liaison

Evelyn Lee, Assoc. AIA

2005 Board of Directors

AIA Regional Directors

David J. Brotman, FAIA Carl F. Meyer, AIA Gordon N. Park, AIA, CDS Clark D. Manus FAIA

Regional Associate Director John M. Cary, Jr., Assoc. AIA

Associate Director, North Douglas A. Smith, Assoc. AIA

Associate Director, South

Evelyn Lee, Assoc, AIA Student Director

Rollin Homer AIA California Desert

Lance Christopher O'Donnel, AIA

AIA California Central Coast Leonard Grant, AIA

AIA Central Valley

Richard T. Conrad, FAIA Virgil C. Hancock, AIA Donald R. Sharp, AIA

AIA East Bay

Eugene Metz, AIA Steven R. Winkel, FAIA

AIA Golden Empire Bruce M. Biggar, AIA

AIA Inland California

Mark Everett Graham, AIA

Gary L. McGavin, AIA AlA Long Beach

John A. Kaytor, AIA AIA Los Angeles Paul A. Danna, AIA

Edmund M. Einy, AIA Paul A. Danna, AIA William H. Fain, Jr., FAIA

Robert G. Hale Jr., AIA Stephen H. Kanner, FAIA

Nick Seierup, AIA AIA Long Beach John A. Kaytor, AIA

AIA Monterey Bay Michael L. Waxer, AIA

AIA Orange County Kevin Fleming, AIA

Evelyn M. Lee, Assoc. AIA Cynthia A. Mabus AIA James T. Wirick, AIA

AIA Pasadena & Foothill

Scott F. Gaudineer, AIA John S. Miller, AIA

AIA Redwood Empire Charles L. Beavers, AIA

AIA Santa Barbara Paul H Poirier AIA

AIA Santa Clara Valley

Frank Edward Jesse, AIA

Richard C. Kirchner, AIA

AIA San Diego

Jack Carpenter, FAIA Larry Allen Hoeksema, AIA

Robert L. Noble, AIA

AIA San Fernando Valley

John P. Grounds, AIA Joel A. Jaffe, AIA

AIA San Francisco

J Paul Bohn AIA George J. Calys, AIA Karen I, Fiene, AIA

Charles A. Higueras, AIA Toby S. Levy, FAIA Thomas E. Lollini, FAIA

AIA San Mateo County Philip J. Bona, AIA

AIA Sierra Valley Christina D.B. Frankel, AIA

AIA Ventura County Howard E. Leach AIA

AIACC Staff

Executive Vice President Paul W. Welch, Jr., Hon, AIA

Director of Marketing and Communications

Lori Reed

Comment

I received the final PDFs for this issue of arcCA, for corrections, while sitting in my car on a side street outside the Le Sage Riviera RV Park in Grover Beach, California. Someone in a café in Pismo Beach had told me there was a public wireless hotspot there.

Surely there is something of architectural significance in the idea—well, no, not the idea, the fact—of someone in a car, downloading onto a laptop computer, through a wireless network based at an RV park, an issue of a magazine featuring award-winning buildings.

And just across the road—the Pacific Coast Highway—is the Grover Beach Amtrak station. It's something one might draw, if one thought about it awhile. Not the train station (though of course one could); the . . . what? "Matrix" isn't right (no mid-air suspensions). "Infrastructure" isn't social enough. "Space"?

It would be a good assignment for the John Lautner described by Jon Yoder in this issue-someone interested in the relationships and not too concerned about making a pretty drawing. Someone who would give equal weight to the seen and the not seen.

As you will see, the regular editorial section of this issue is about drawing and, more specifically, about attitudes toward drawing and the use of drawing. We have excluded the most obviously utilitarian sorts of drawings—construction documents—not because we think them dull, but because we intend to devote the first issue of 2006 to them.

Less intentionally, we're delaying until the fourth quarter of this year an article about the architectural illustrations of Carlos Diniz. The editor dawdled in selecting the illustrations to print, and then we ran into a further delay in securing highresolution scans. But they (along with Peter Dodge's commentary) will be something wonderful to look forward to

The drawing on the cover is by Rob Quigley, this year's AIACC Maybeck Award winner. We're pleased for the second time to be able to publish the annual AIACC and Savings By Design Awards in a special color section.

Tim Culvahouse, AIA, editor


You Learned at Hard Knock University. Time for your class reunion...

CAD Pilot Jump School for architectural professionals



- > Real World, Project Based Environment
- ➤ Maximum Hands-on In Minimum Time
- > Includes: Upgrade Training, Application Training, Implemenation, & People Skills

Information/Registration: 1-800-511-8020 www.cvis.com








Consultants in Noise & Vibration Control

- Microelectronics
 - Offices
 - Test Facilities
- Research Laboratories
 - Industrial plants
 - Hotels and Resorts
- Schools and Universities
 - Convention Centers

883 Sneath Lane, Suite 150 San Bruno, CA 94066 USA

Tel.: 1.650.358.9577 Fax.: 1.650.358.9430

E-mail: nadine.hastings@colingordon.com www.colingordon.com



Architects & Engineers

Architecture • Civil engineering • Electrical engineering Mechanical/HVAC engineering • Land surveyor Landscape architecture • Interior design Acoustical engineering · Planning · Traffic engineering



JAN P. BLACK, Agent Lic.#0548759 Auto - Life - Health - Home and Business 32150 Yucaipa Boulevard Yucaipa, California 92399 (909) 794-9000



Home and Landscape Innovations in Stone, Granite, Slate, and Natural Materials



COMING SOON!

408,996,4500

1505 DeAnza Boulevard . Cupertino GRANITEROCK.COM



WHAT DOES A LOTUS HAVE TO DO WITH INNOVATIVE ENGINEERING?

Scientists have discovered lotus pollen dating back to the Cretaceous Period, 135 million years ago. Having gone through countless geological changes, most ancient plants have died out; but the lotus survives, thanks to its perennial root and the strong natural structure of its seeds and petals.

At Degenkolb we realize that nature is the mother of invention. Our reputation and 60 years of experience are strongly rooted in making use of a building's existing strengths and designing new buildings that, like the lotus, will adapt to environmental changes and withstand the tests of time. Based on our commitment to innovation and earthquake safety, we are focused on environmental sustainability, disaster resilience, security, earthquake hazard mitigation, and performance-based engineering.

For more information about what Degenkolb can do for you, please call 415.354.6555



COLLABORATE





Whether designing innovative hospitals, state-of-the-art laboratories, or distinctive civic facilities, HDR provides a full range of architecture and engineering solutions for clients nationwide. In California, HDR has offices in Folsom, Lake Forest, Mountain View, Oakland, Pasadena, Riverside, San Diego and Santa Ana.

For career opportunities, please visit www.hdrinc.com/architects.

AAP EOE M/F/D/V



You can already tell exactly what kind of house it's going to be.



Á

The right windows and doors help bring your plans to life beautifully. Specify Marvin, and you're assured of complete design flexibility and better-performing windows and doors with superior aesthetics. That includes furniture-grade interiors, consistent sight lines and the tightest tolerances possible.

Call 1-888-544-177 or visit marvin.com



CAD MANAGER BOOT CAMP '04

30+ Intense hours of Management Training delivered by experts.



Learn How To Manage Your: Staff, Tools, Work, & Environment

Proven curriculum you won't find anywhere else!




Information/Registration: 1-800-511-8020 www.cvis.com

Locations throughout California. See our other ads in this publication for more software and services.



visit our website: www.coarchitects.com

5055 Wilshire Blvd, Los Angeles, Ca 90036 ph 323 525 0500



UPDATE

handbook on project delivery

AIA California Council

In response to the overwhelming need for information about today's complex and innovative project delivery methods and trends, the American Institute of Architects. California Council (AIACC) has developed a comprehensive guide for architects, their clients and contractors, to assist in important building related decision making. This resource provides members of the building team important information regarding project delivery. The AIACC recently released the new Update which is now included in the Handbook on Project Delivery. This addition features 15 new case studies providing a thorough evaluation of many different delivery methods, assisting in the selection of the most appropriate method for each project.

To order your copy of the *Handbook on Project Delivery* or the new *Update*, visit aiacc.org and select "purchase" or call 916.448.9082 for an order form.

Contributors

Tulay Atak is an architect and a doctoral candidate in the Department of Architecture and Urban Design at UCLA.

Lauren Weiss Bricker, PhD is an associate professor of architecture and director of the Archives-Special Collections in the College of Environmental Design, California State Polytechnic University, Pomona. Dr. Bricker is Chair of the State Historical Resources Commission in California and co-chair of the Commission's Committee on the Cultural Resources of the Modern Age. She is a co-author of forthcoming *Mediterranean Revival House* (Abrams), and is currently working on "The Pragmatists," a study of the American response to the form and ideology of European Modernism, supported by a fellowship from the Clarence S. Stein Institute of Urban and Landscape Studies, Cornell University.

John Chase is the Urban Designer for the City of West Hollywood. His last book, *Glitter, Stucco & Dumpster Diving* won a PEN USA nomination for best books on the visual arts in 2001. His next book, 2000+: 30 Los Angeles Buildings by 30 Los Angeles Architects, will be published by Monacelli Press in Spring 2006. Mr. Chase is a former architecture critic for the San Francisco Examiner and former Disney Imagineer. He is a member of the arcCA editorial board.


Anthony Denzer is Assistant Professor of Architectural Engineering at the University of Wyoming. This article was drawn from his doctoral dissertation, "Gregory Ain and the Social Politics of Housing Design" (UCLA, 2005). He also received an M.Arch. from the University of Kansas.

Wendy Kohn is co-author of *The City after the Automobile* and editor of several architectural monographs. She is currently an architectural consultant and columnist for the magazine *My House* and a member of the **arcCA** editorial board.


Perry Kulper is an architect and SCI-Arc Faculty member living in Los Angeles.

Alexander Ortenberg is an architectural historian, a practicing architect, and an architectural artist. He received his PhD from UCLA, his dissertation focusing on the evolution of architectural representation and on the evolution of architectural professionalism. He teaches at Cal Poly Pomona and is the principal of Ortenberg Architecture. He is a member of the AIA, the Society of Architectural Historians (SAH), and the American Society of Architectural Illustrators (ASAI).

Jon Yoder is completing a doctorate in Critical Studies in Architectural Culture at UCLA. His dissertation takes the ocular-centric projects of John Lautner as lenses through which to focus on issues of experiential and projective vision. Drawing on visual media theory and existential phenomenology, it is the first sustained study of embodied visuality in architecture. He has also worked as an architectural designer with Pei Cobb Freed & Partners, The ZGF Partnership, and SPF:Architects.



[Introduction]



Alexander Ortenberg, PhD

When discussing architects' practices, scholars and professionals alike tend to emphasize the longevity of our craft's mental and physical instruments. Even as recent technological and theoretical developments made some of them obsolete and challenged some others, little has been done to rethink the history of the architect's tools. As to architectural drawing—arguably the oldest and the most stable of those devices found in our conceptual toolbox—we have become accustomed to the notion that visual representation emerged after a certain threshold of structural complexity and/or sophistication of architectural forms had been surpassed.

It is tempting indeed to interpret four-millennia-old papyri found near the Egyptian city of El Ghorab as a prototypical construction document. Practicing architects might also be eager to construe late medieval drawings as a form of communicating the future building to the patron and the public. Furthermore, the sketchbook of thirteenth-century master-builder Villard de Honnecourt might appear not unlike those that turn-of-the-twenty-first century masters such as Alvaro Siza still carry around with them. Finally, Rafael's letter to Leo X advocating the

use of floor plans, elevations, and sections seems to present evidence of a completely modern approach to design emerging in the early sixteenth century.

Undoubtedly, these artifacts indicate a long history of drawing being one of architects' major tools. They should not, however, be misconstrued as proof that contemporary means and conventions of architectural representation are nothing but a refined version of the eternal architect's toolbox. Magnificent as they are, the elevations of late Gothic cathedrals could not be considered as an exhaustive means of representation. Unlike our contemporary drawings, which imply the representation of depth—and this includes orthographic projections—medieval drawings depict only the plane of the main elevation.


Moreover, even as some forms of architectural representation have indeed displayed remarkable longevity, their social and cultural roles have gone through tremendous changes. Drawing, which is now considered the most transparent and universal way to convey design ideas to a wide range of agents, was once used to draw the line between the architect and his learned patron, on one side, and the unenlightened mechanic, on the other. The Renaissance theorist and artist Luca Pacioli—whose 1509 treatise was a major tour de force in establishing modern conventions of graphic representation—was convinced that the rules of geometry were too abstract to be grasped by mere craftsmen. Written two centuries later, a treatise by French Royal architect Ch-A. d'Aviler attests to the fact that late-seventeenth century architects searched, in their communications with builders. for the best written and verbal expression and did not rely on graphic explanation. It was only by the middle of the eighteenth century that English and French theorists proposed extending the ability to read architectural drawings to the "whole Body of Artisans and Mechanics." Even then, many of these theorists made clear that they meant only the masters of the trades. The "servile and labouring Order of People" was still condemned to have no other knowledge than what was absolutely necessary for the perfection of their manual skills.

Nineteenth-century democratic ideals—mixed with architects' struggle for their professional authority—brought a new approach to the art of architectural representation. It became perceived as a universal language to be understood by the client

and the foreman, by masons and carpenters, by architectural critics and by the general public. Coinciding with the significant reduction in the cost of papermaking, these social and cultural developments led to a true explosion in the production of architectural drawings. In a letter written in 1867, the French architect Charles Garnier reported that, while working on the project for the Paris Opera, his office produced 30,000 (!) sheets of working drawings. Garnier was well known for his efforts to promote architecture as fine art. His inscription for his tombstone did not, however, mention any of his artistic achievements but said, merely, "Here lies Charles Garnier, the son of a shoemaker," It was this dual self-perception as both an artist and a laborer that made him as proud of his mode of production as he was of the final fruit of his labor.

The architectural profession arrived in California around the turn of the twentieth century. As Reyner Banham once stated, by this time "being unable to think without drawing became the true mark of one fully socialized in the profession of architecture." And yet, the drawings discussed in this issue of arcCA demonstrate that their role extends beyond the widely recognized functions of learning new ideas, developing design concepts, and communicating them to collaborators and clients. They clearly indicate that architects have used their representational skills to make a statement of who they are vis-à-vis their colleagues, society, and the history of our profession. •





Let Me Illustrate

Tulay Atak

This short essay was written after an interview with Neil Denari that took place on June 4, 2005. Rather than explaining Denari's work or quoting his words verbatim, the essay addresses a specific comment Denari made during the interview on drawing as illustration and attempts to extrapolate the notion of illustration in architecture. I am grateful to Neil Denari for his generosity with his time.

Neil Denari calls his drawings illustrations. Images in a book, a manual, a newspaper, or a magazine are illustrations; hence, the medium where the image is found plays a role in determining how an illustration works. A diagram, a cartoon, a graph are illustrations; hence, the kind of image plays a role in determining what an illustration is. What place does an illustration hold between drawing and design in architecture? What kind of a practice does it entail?

As Mario Carpo has shown, the introduction of images into architectural treatises in the Renaissance, concurrent with the invention of movable type, made an enormous impact on architecture. The volatile category called "illustration" implied not only the mechanical reproduction of drawings, but also a transformation in the production of architecture. Alberti, for instance, preferred to translate images into text and avoided visualization. With his distrust for illustrations at the dawn of mechanical reproduction, he devised a method for the notation and reproduction of three dimensional shapes based on numeration rather than visualization. He claimed that with his method, identical copies could be produced; two sculptors separated by distance or

time could produce the two halves of a sculpture which would form a complete whole if brought together. Already implied in Alberti's work was the practice of the architect as the writer of codes as opposed to an illustrator.


In Alberti's case, the resistance to illustrations was founded on a criterion of precision. Prior to the intrusion of illustrations, written codes and sequences of operations were considered to be more precise for the transmission of architecture than an image. Hence, the adjacency of the two terms "precision" and "optical" was not an easy coupling; rather it was an acculturation that developed over a period of time in various fields. Art historian Svetlana Alpers has described the beginnings of this adjacency as the "art of describing," in relation to a set of practices from mapping to projection.³ When Marcel Duchamp coined his own "precision optics," the two terms were meshed onto each other in the world of visualizations. 4 Duchamp, himself a student of technical drawings, played with the situation of illustration between drawing and design, between image and concept. In the set of rotating drawings named "rotoreliefs," he relocated precision in the corporality of vision.

WHAT, EXACTLY, IS AN ILLUSTRATOR'S PRACTICE?

Illustration always has an end beyond itself. It illustrates something other than itself, and it can never be found outside media—be it a book, a magazine or a newspaper; or independent of its referent—be it a text or a product. It is embedded. Illustration has a clear intent: to deliver information. In most cases, illustration is a commercial activity; hence, the delivery of information is also the delivery of a mood conducive to its reception. Simply put, illustration is a mediating practice. Illustration is a condition of architectural drawing in which drawing has no autonomy but is the embodiment of design.

Illustration is not an art; the closest it comes to art is that lowly version of art, graphics. No less coded than written codes and instructions, illustration operates with visual codes. It requires a specific set of skills, which can be acquired and repeated. It has already-set types of drawings.


Instead of inventing new types of drawing, as Rossi and Morphosis have done, Neil Denari's *Gyroscopic Horizons* is full of standard drawing types. The two images included here, the section and



above: Page from the sketchbooks: Corrugation and perimeter studies for possible projects; right page: Prototype house, Tokyo, Japan, 1993: Section and axonometric drawing.

axonometric drawing of the Prototype House in Japan (1993), are standard architectural drawings. While drawing types remain constant, design changes. The constancy and change are traceable in Denari's sketchbooks, as well. Hence, illustration has less to do with tools—like ink or graphic software -and the final medium where it will be found-like Mylar, notebook, plot or a website—than with standard drawing types. The standardization of drawing types is a part of illustration. In illustration, the passage from ink and Mylar to the computer screen is smooth. Here, a parallel might be drawn with Zaha Hadid's work. Taking perspective as the visual code of architecture, Hadid's early paintings were not the invention of types but the distortion of already existing ones. Hadid's paintings were illustrations of her architecture.


The visual code of illustration leads to visual precision. Precision on its own does not predetermine architectural form. Rather, precision is about how one deals with form. Here may be the key role of illustration: If illustration is extended from a condition of architectural drawing to a design practice,



design becomes precision design. The lesson of Duchamp's "precision optics" might well be an optical tangibility. Precision design is clear both in terms of its conception and in terms of its projection and mediation from drawing to building. This is a passage from precision optics to precision design, from architectural graphics to graphic architecture. •

Illustration is not an art; the closest it comes to art is that lowly version of art, graphics.

- Mario Carpo, Architecture in the Age of Printing: Orality, Writing, Typography, and Printed Images in the History of Architectural Theory. (Trans. Sarah Benson). Cambridge, London: MIT P, 2001. Carpo's recent essay "Drawing with Numbers: Geometry and Numeracy in Early modern Architectural Design" extends the problem of images in architectural theory to numeration practices from fifteenth century onwards. JSAH 62:4, 2004: (448-469).
- 2 Alberti, On Painting and Sculpture (Ed. and trans. Cecil Grayson.) London: Phaidon, 1972. 128-130. See also Mario Carpo, Architecture in the Age of Printing, 122-123.
- 3. The vast bibliography on the history of optical precision is heterogeneous: Svetlana Alpers, The Art of Describing: Dutch Art in the 17th Century. Chicago: University of Chicago P, 1983. Michel Foucault. Birth of the Clinic: an Archeology of Medical Perception. (Trans. A. M. Sheridan Smith.) New York: Vintage Books, 1973. Barbara Maria Stafford, Body Criticism: Imaging the Unseen in Enlightenment Art and Medicine. Cambridge, London: MIT P, 1991. Picturing Science, Producing Art. (ed. Peter Galison and Caroline A. Jones) London: Routledge, 1998. A forecast of optical precision was given by Arnaldo Momigliano's pioneering work on history and the antiquarian. Momigliano also suggested a link between the development of modern engineering and the practices of the antiquarian. In this respect, the figures of Piranesi (1720-1778) and Auguste Choisy (1841-1909) are noteworthy in the establishment of the visual field governed by precision in architecture.
- In the 1920s, Duchamp carried business cards which described his profession as a "precision oculist." For Duchamp's precision optics, see Rosalind E. Krauss, Optical Unconscious. Cambridge, London: MIT P, 1994. p. 95-142.



Representing Beyond the Surface

Perry Kulper

See also Color Plates 4 and 5.

The projective roles of the architectural drawing in the discipline of architecture are simultaneously exhilarating and daunting. The formal predilections of Modernism, frequent shifts in cultural paradigms, the displacement of manual drawing by keyboard procedures, and the increasing links between software applications and material fabrication processes suggest a reassessment of the role of drawing.

These working notes are an attempt to broaden considerations surrounding the drawing through the cultivation of its various levels of communication, the stimulation of its latent content, and the catalyzing of its speculative roles. These thoughts are an attempt to augment the homogeneous and reductive practices of drawing and to reestablish its imaginative, generative, and creative agencies.

To overcome the legacy of reductive representational practices, we should conceptualize the construction of drawing as more than a tool for problem solving, organization, or expression. A number of interesting questions deserve reconsideration: the distance between the architect, the drawing, and construction; the differences between varied drawing types and their vested authorities; the debates over

left: David's Island

white page versus black screen; the temporality of drawing and its reminiscent and speculative potentials; and the dimensions of experience that perpetually elude the conventions of drawing. While not at the forefront of educational or professional discussions, engaging the spirit of these questions might allow the architectural drawing to reassert its formidable creative agency, while participating in the continuities of cultural imagination.

Motivated by ideas and language on the one hand and by geometry and material projection on the other, the architectural drawing has undergone a multitude of developments, interpretations, and transformations. It has defined and been defined by complex cultural circumstances. In my own work and my work with students, I am interested in the drawing's capacity to represent these complex situations. I am optimistic about the conceptual and speculative potential of mark-making, valuing what is known as well as the accidental and unborn; the margins and figures count alike.

Unlike more exclusionary positions, my work employs multiple representational techniques simultaneously, allowing the drawing to communicate on several levels. The use of indexical sets, notation, diagrammatic assemblies, material indications, language, and other generative marks cultivates latent relations, facilitating the drawing's investigative potential. Manual, digital, and hybrid techniques are all possible. Local "ecologies of potential" emerge from this choreography, teasing out spatial possibilities from the drawings.

The avoidance of premature ideational, geometric, and material reduction is one of the primary ambitions of my work, and a necessary ingredient in the imaginative life of the drawing. The act of drawing itself becomes a form of discovery of the logics and structure of the work.

In the Strategic Plot for the David's Island Competition, for example, speculations about content and programmatic structure emerge from a number of sources, not the least of which is the imagined potential in the space of the Plot itself. Like a game board or a map, it occupies a representational territory between landscape and architecture, incorporating notations for future development. Material configurations coalesce with diagrammatic and durational marks, opening representational bor-

Motivated by ideas and language on the one hand

and by geometry and material projection on the other,

the architectural drawing has undergone


a multitude of developments.

interpretations, and transformations.

ders and cultivating more fluid ideological, material, and temporal assemblies.

In the Fast Twitch drawing, I set out to explore desert occupations linked to ground, sky, and horizon. This drawing includes territorial marking, notation, language, and material indications. As it developed, my interests expanded to include hybrid archetypes, subtle shifts in perceptual awareness, incompleteness, and relations between rhetorical structuring and embodied experience. The drawing examines these interests through varied communicative levels, opening analogical and intuitive means towards the generation of a proposal for desert occupation. Conventional drawing types intermingle with other invented representational techniques, enabling the emergence and eventual synthesis of a range of ideas, with material and spatial ramifications nearly impossible through more traditional drawings.

The Metaspheric Zoo (a cross between "metaphor" and "atmosphere") is a speculative proposal for the Prague Biennale. It is the first in a series of preparatory drawings to discover and theo-




Fast Twitch Site

rize the zoo. Its primary topical, relational, and programmatic attitudes were established through an image combining characteristics of a puzzle, a geographic matrix, and a taxonomic inventory. Ambient surfaces tease coded and indexical marks. Instrumental practices are crossed with language and invented "characters" toward the creation of a synthetic, incomplete, and strangely familiar whole. From this beginning, programmatic interests in botanic surfacing, a roving taxidermy, and a vessel for obsolete atmospheres emerge, confronting the disparate impulses of instinct and desire which are all but eradicated from our over-programmed society.

Although culturally grounded, drawing is a kind of personal cartography in which circumstance and creative identity coalesce toward spatial configurations. Drawing is a risk, and confronting the white surface, or black screen, is an act of violation. It is an assault on whiteness and abstraction.

By engaging varied and shifting levels of communication (in many ways analogous to our embodied experience of space), the speculative, imaginative, and latent capacities of drawing may make it possible to forget, momentarily, the scenic surface of the image. The possibility of seeing behind, beneath, and through the space of drawing—and the drawing of space—toward greater cultural agency and communicative range is the promise and provocation of architectural representation. Though the parameters have radically changed, the architectural drawing remains an unfinished and tantalizing project.

•



Gregory Ain:


Drawings against Photographs

Anthony Denzer

When Julius Shulman visited his friend Gregory Ain one day in 1937, he unexpectedly witnessed a scene that would forever shape his understanding of the practice of architecture. Ain and his partner George Agron were designing a small house, and Shulman found them debating the placement of a wall between two rooms. "They had tracing paper over the board," the photographer recalled. "They were going back and forth on that one line." Even half a century later, Shulman remained astonished at the level of intellectual rigor applied to a seemingly mundane problem: "I have never forgotten that line. Here are two mature men—young men of course, but they were mature— ... They were working on one line!" ^I

Of course, all architects give careful consideration to the placement of lines on a floor plan, but a review of Gregory Ain's architectural drawings shows that his working method was especially meticulous. ² Clients were amazed at the number of alternatives he had studied; a colleague said he "suffered" over his plans at the expense of his private life. ³ Ain developed this method simply because there was so much at stake. Throughout his career, he sought to construct bold new social relationships, and yet he

left: Gregory Ain, Dunsmuir Flats view from street (Los Angeles, 1937)



This ten-unit complex of attached row houses was the most progressive project of his career, as it challenged practically every convention of postwar housing: its social organization, economic administration, and


physical form.

also wanted to minimize his structures in order to save construction costs. The difference between 960 and 1,020 square feet might mean the difference between a built and an unbuilt project. At the drafting table, every quarter-inch counted.

One of his most difficult projects, which clearly shows how his "suffering" carried significant social and architectural meaning, was Avenel Homes (Los Angeles, 1946). This ten-unit complex of attached row houses was the most progressive project of his career, as it challenged practically every convention of postwar housing: its social organization, economic administration, and physical form. But during the design process some of Ain's avantgarde ideas were rejected by local officials from the Federal Housing Administration (FHA). In the initial plan, Ain designed a kitchen which was almost completely open to the living room, a pioneering attempt to enliven the work of the housewife by connecting it to the social life of the house. When the FHA demanded a closed kitchen, this important relationship was destroyed. In addition, the original design also used the dining table to bridge between the kitchen and living room, which was an eminently reasonable strategy for saving space in the 908square-foot units. When this feature was eliminated, residents were forced to accommodate a freestanding dining room set in the compact living room. Many families responded by expanding the living room four feet, eliminating the south overhang that Ain had considered essential to the plan.

FHA officials also objected to Ain's original plan for a "double bathroom," which located the toilet and sink in one compartment, with the bathtub and laundry in a separate adjacent room. This plan would have accommodated simultaneous activities while maintaining privacy, an eminently logical and convenient feature. Again, Ain creatively interrogated the basic relationships between typical functions and their architectural planning. And, again, he was defeated. The bathroom, as built, was a common square room containing the toilet, sink, and bathtub. Summarizing the conservative institutional logic that Ain battled, Alfred Steinberg argued: "FHA opposes the novel and untried because it represents risk." ⁴

But when he made presentation drawings for publication, Ain used the "original" floor plan, which included the open kitchen, built-in dining



Gregory Ain, Dunsmuir Flats plan (Los Angeles, 1937)

table, and double bathroom, even though these innovations were not built. This post-construction idealization of the project was consistent with Ain's earlier habits and his general belief that architectural publications should convey ideas rather than mundane realities. In the 1990s, at least three new Avenel residents rebuilt the kitchen according to Ain's original plan, a sympathetic "restoration" effort that raised quite interesting critical questions about the meaning of the "original."

Ain hired Julius Shulman to photograph the Avenel project, and Shulman might have been expected to have a heightened sensitivity to Ain's work, given his 1937 epiphany as well as his belief that the purpose of architectural photography was to recover and communicate the design's "true" intentions. 5 Still, Ain found that Shulman's images could not properly convey the progressive aspects of the project that he wanted to promote—the social relationships—in part because Shulman could not photograph what had not been built. Indeed, photographs of his projects frequently disappointed Ain; he worked with seventeen different photographers between 1936 and 1952, as if he were constantly, fruitlessly, searching for the artist who could correctly portray the underlying architectural ideas. At the end of his career, Ain told David Gebhard with a certain modest pleasure: "You know, I have many houses that have never been photographed at all." 6

Ain's approach to architectural drawings was always calibrated against his curious and com-

plex set of attitudes towards architectural photography. When he was asked to reflect on his achievements late in his life, Ain spontaneously launched into an extensive critique of photography and architectural publishing. He had become so dismayed at magazines' habit of favoring photographs over plans that he audaciously proposed a moratorium on the use of photographs in all architectural publications. It was a serious suggestion; He apparently developed the idea while he was a prominent educator in the 1960s, and he repeated it twice in separate interviews in the late 1970s. He believed that the important architectural ideas—social relationships—were found in the floor plan. And he genuinely failed to understand why magazines represented his work primarily through photographs rather than drawings.

He admitted his own work had contained "far less 'eye-appeal' than contemporary work which may have had a different motivation." And he insisted: "public relations was never a factor in my practice ... the camera has never been part of my problem." Ain's anxieties about photography, then, shaped an ideology about how his project would be produced, disseminated, and ultimately received.

Ain was an excellent draftsman and he could draw immaculate aerial perspectives due to his mathematical mind and his training under Richard Neutra. But it is abundantly clear that Ain's illustrations were not intended as *objets d'art*; they were only produced, when needed, to convey the project to his client so that it might be built. In fact, a number of

Ain's projects did not have pictorial drawings at all. Most significantly, Ain did not follow Rudolph Schindler's practice of making stylized illustrations for exhibition, nor Neutra's habit of using color for atmospheric effects. Ain's ascetic, hard-line drawings were utterly "rational" and documentary, although he did sometimes prefer to show the building in an "ideal" state. A preponderance of his perspective drawings were only completed on trace paper, a material unsuitable for exhibition or for posterity.

Ain was especially disappointed that one image, in particular, often represented his entire career: an exterior view of Dunsmuir Flats (Los Angeles, 1937). This photograph, by Julius Shulman, showed the four-unit apartment building as a lean, streamlined "machine-in-the-garden," the articulated structure appearing to cut through the landscape like a freight train. Because the image emphasized architecture-as-volume and the building's repetitive form, it appeared to be a perfect illustration of the International Style. More than any other, this image garnered national recognition for Ain. It was published widely in period magazines, and it was displayed at the Museum of Modern Art. ⁸

In a late interview, Ain claimed that he resented over-publication of the iconic Dunsmuir Flats photograph because the elevations were "simple extrusions of the plan." This statement was patently insincere, since he went to so much effort to craft the solid-void relationships between the slab overhangs and the strip windows, for example, but in essence it was an effort to distance himself from Shulman's image and deny authorship of it. Ain insisted: "I never liked the way they looked, though the plan was really extraordinary." ⁹ Indeed, the plan inventively solved several problems, and on this basis Ain considered Dunsmuir Flats his most successful project.

Yet, when Ain referred to "the plan," he meant an idealized redrawing of the plan; as at Avenel Homes, here he also elided the fact that the building was not built as he wished.


Early perspectives and plans show that Ain intended that each unit would have a geometric integrity of its own and then participate in an idealized system where each would be staggered in plan and section at identical intervals. The building as constructed, however, compromised the purity of


this system in several ways. First, the two rear units were built at the same floor level and therefore did not "interlock" at the roofline. Second, the four units were not, in fact, all attached. Ain was forced to "break" the building into two pieces with a three-foot clearance in between the second and third units. In reality, as a close reading of Shulman's photograph demonstrates, Dunsmuir Flats was not the perfectly platonic mathematical game that Ain sought to portray. When he made presentation drawings of Dunsmuir Flats for publication, Ain "restored" the building to its ideal state.

If Ain's habit of redrawing and idealizing his buildings indicated his suffering—and his perfectionism—it also placed him within a strong tradition among architects, including Frank Lloyd Wright and Andrea Palladio. These architects, too, used the mutability of drawing as a medium to elide issues of contingency that were considered irrelevant to the architectural ideas. What made Ain's case significant and instructive was his insistence on using drawings as a means to compensate for the limitations of photography.

•

- Julius Shulman, interviewed by Taina Rikala De Noreiga, Los Angeles, California, January 12 & 20, February 3, 1990, Archives of American Art, Smithsonian Institution, Tape 4, side B.
- Ain's drawings are archived at the Architecture & Design Collection (ADC), University Art Museum, University of California, Santa Barbara.
- James Garrott, quoted by Esther McCoy, The Second Generation (Salt Lake City: Peregrine Smith Books, 1984), 134.
- 4. Alfred Steinberg, "FHA-Profits Before Housing," The Nation 168 (January 1, 1949), 11-13.
- Julius Shulman, Photographing Architecture and Interiors (New York: Whitney, 1962), 2.
- Ain, interviewed by David Gebhard and Harriette Von Breton, June 19, 1973. Transcribed notes, David Gebhard papers, (ADC), 2.
- Ain, interviewed by Thomas S. Hines, April 25, 1977. Tape recording courtesy of Thomas S. Hines.
- 8. Elizabeth Mock, ed., Built in U.S.A., 1932-1944 (New York: Museum of Modern Art), 1945.
- 9. Ain, interviewed by Gebhard and Von Breton, op. cit.






John Lautner:

Diagramming Vision in Los Angeles

Jon Yoder

By all accounts, Los Angeles architect John Lautner was a poor draftsman. Architect Wes Peters, Lautner's friend and fellow apprentice with Frank Lloyd Wright at Taliesin, even called him "the most terrible draftsman I ever saw in my life." Lautner admitted as much: "I took drafting when I was in high school and I couldn't keep the pencil sharp. I couldn't make a neat drawing and I knew the typical school, all they do is grade on neat and then to hell with the ideas, and Mr. Wright had ideas so I went for that." This distinction between neat drawings and substantive ideas is more than the defensive response of a messy student-it reflects a common distaste among Modern architects for what was widely considered to be the superficial pictorialism of the Beaux-Arts tradition. At Taliesin, Lautner purposely used his poor drafting ability to deflect the rendering tasks that apprentices were typically assigned during their tenure with Wright. By consciously focusing on ideas instead of on line weights, Lautner hoped to avoid the lures of mimesis and "paper architecture."

Instead of drafting, he preferred the physical tasks of building. His experience with masonry and pipefitting at Taliesin, coupled with his supervi-



Beyer House

sory work for a building contractor during World War II, gave Lautner a direct feel for construction systems and materials. This knowledge helped him to achieve many ingenious structural solutions throughout his career. In fact, his penchant for structural efficiency and bold concrete forms have led some to align Lautner's architecture with the work of structural expressionists such as Oscar Niemeyer, Eero Saarinen, and Kenzo Tange. These were, after all, the contemporary architects he most admired.

A closer look at one of Lautner's seemingly crude drawings, however, reveals a greater concern for program than for construction. His schematic plan for the Beyer House is essentially a programmatic diagram of room functions, furniture arrangements, material notations, site conditions, and viewing angles. Seen as a presentation drawing, it is certainly unpolished, even child-like. But as a working diagram it is actually extremely sophisticated. It contains an enormous amount of information. No mark is superfluous. Every line means something. Of

course, many architects of Lautner's generation employed similar "bubble" diagrams, but few ever managed this level of complexity. And most surrendered what began as curvilinear forms to the rectilinear rationale of the grid during design development. As Lautner fleshed out his designs, however, they often kept their curvaceous character.

Lautner often began projects by taking a topographic map to the building site and indicating desirable viewpoints and orientations directly on the map. Then, practicing the creative gestation he learned from Wright, he would return to his office and spend days trying to visualize the project. As Lautner explained, "It's thinking right from scratch and having a major idea, from inside. I've never designed a façade in my life." Although many other architects have made similarly staunch "form follows function" assertions about their inside-out design processes, Lautner's claim was largely justified. He rarely designed in elevation, diagramming projects instead in plan and section. After meeting with the

client to verify program, he would then hand these seemingly rough diagrams to his staff to produce construction drawings under his supervision. His drafters were often surprised at the level of detail and accurate scale in diagrams that initially looked child-like.

Of course, this design process sounds similar to those of other star architects. Frank Gehry, for example, is known to generate napkin sketches of general building profiles from which his staff extrapolates built form under his guidance. Still, although Lautner's forms are often as sculpturally plastic as Gehry's recent buildings, they resulted from an extremely different impulse. Gehry's surfaces undulate mainly for effect from the exterior, while Lautner's forms curve primarily to accommodate views from the interior. Reflecting what Erwin Panofsky labeled the "spheroidal" shape of human vision, Lautner's bulbous spaces diagram the alliance of site and sight. As Lautner explained, "Usually in the hills you have a panoramic view that people are interested in right away, and so most of my things are curved." Even his innovative spanning systems—trusses, waffle slabs, and concrete shells—were employed largely to keep the views from his buildings as free of visible obstructions as possible. By using these long-span devices to eliminate intermittent walls and columns, Lautner opened the viewing "apertures" of his wideangle spaces. If Gehry's buildings pose for cameras, Lautner's houses operate as cameras.


Even during his early days with Wright, Lautner's architectural attention was clearly focused on constructing views. In a 1937 "At Taliesin" newspaper article, he compared the behavior of Wright's Roberts House at Deertrack, Michigan to that of a human eye: "The house itself is literally looking toward the lake because the living room roof and ceiling pitches up like one's eyelash under a visor to the sky, leaving nothing but glass between you and the view." During his later career, Lautner continued to note "eyelids" and "eyelashes" in his schematic designs. These often found architectural expression in moveable shades and deep roof overhangs that simultaneously shield the sun and frame distant views. Sightline notations and optical specifications such as "CHK view ON SITE!" also occur frequently throughout these drawings. These notes and arrows might seem crude, but they actually require more from the architect than is typically expected-more

time on site (and sight), and less at the drafting table.

On one hand, because Lautner never became a very good draftsman, his reliance on graphic representation techniques was minimal. He was no captive of the two-dimensional surface, and neither are his buildings. On the other hand, neither was Lautner the child-like primitive that many assume. His curving, free-flowing forms were rarely the result of purely intuitive gestures. Although his schematic drawings often look like basic bubble diagrams, they are more than formally vague placeholders for future program; they are actually sophisticated design drawings that contain incredible detail and indicate precise layouts of space and vision. They are diagrams that surely asked and answered more questions than highly polished presentation drawings would have.

Drawings, for Lautner, were necessary devices for achieving the final building, but they were simply not valued as finished artifacts. This attitude hampered Lautner's public recognition in the 1970s, when a major East Coast publisher wanted to issue a monograph on his work. The attempt was stymied when Lautner refused to "clean up" his drawings for publication. In order to be published, they would have had to become more like the presentation renderings he despised. "They just don't get it" was his continued refrain. Drawing and construction were both transparent activities for Lautner—merely means to an end. He could readily see beyond both activities to imagine their implications. Graphic techniques and construction technologies were essentially lenses through which he visualized his projects. Like Lautner's camera houses, his drawings are less for looking at than they are for looking through. They are operative diagrams of ocular desire. •

Note: The author would like to thank Frank Escher and Brian Hart of the John Lautner Archive for their valuable assistance. See also The John Lautner Foundation website: www.johnlautner.org.



Sugar Daddy

Drawing

Berlage's


Exchange

Wendy Kohn

"It's a stair I used every day," remembers Daniel Castor as he contemplates "Sugar Daddy," his luminous drawing of the entry to the Chamber of Commerce in H.P. Berlage's 1903 Amsterdam Exchange. Castor first encountered the building he describes as a "ship in dry-dock" while traveling around Europe after college graduation. The structure known as the Beurs "struck a chord in me," he admits. In 1993, Castor won a Fulbright to return to Amsterdam during a break from Harvard's Graduate School of Design. Several grants and four years later, he finished an analysis of the Exchange that's been published in book form (*Drawing Berlage's Exchange*, Rotterdam: NAi Publishers, 1999), exhibited in Los Angeles and Rotterdam, and recognized as both masterful and magical.

His research began with a series of probes: different ways of revealing the ideas behind Berlage's "inscrutable" building in drawn form. These were plans, isometric projections, even a sixteen-foot-long, continuous elevation. But it was Castor's desire to convey his own wonder at a building many Dutch saw as "ugly and boring" that led him to develop his own technique. "That's beautiful," declared his Dutch friends when he completed his first "deep





The more your eye flows around and through the volumes of space depicted, the more you start to see solid and void, motion and stasis, lightness and weight simultaneously



space" perspective drawing, "and if that's the building, then it's interesting."


In his study, Castor focused on the zone of the building where Berlage, credited as Holland's first modernist, pierced the austere flatness of his exterior elevations. The massive Exchange's perimeter and its immediately adjacent interiors proved an "unending" subject: "the more I looked, the more I saw." Castor's eight "jellyfish" drawings, his term for these inside-out studies, possess this quality as well.

At first they seem factual: a careful transposition of three-dimensional, built form onto a two-dimensional plane. But the more your eye flows around and through the volumes of space depicted, the more you start to see solid and void, motion and stasis, lightness and weight simultaneously.


At 2 ft. x 4 ft., these large drawings suggest the interaction between calculated design and experienced tectonics in a way photographs or typical renderings are rarely capable of. Rather than definitive cuts through surfaces, as in conventional architectural drawings, slow fades move your eye from what is portrayed to what is left out. The technique extends the implied space of Berlage's Exchange right out to the viewer's own. It manages to evoke and analyze at once.

Working on the Exchange entirely by hand meant that each jellyfish drawing was essentially an experiment, a record of choices made during the rendering process. Even though the jellyfish technique allowed Castor to show many competing aspects of a single view at once—inside and out, above and below, surface and depth—he reached a moment in every drawing when he had to surrender the ambition to convey everything he perceived.

For two subsequent projects, on Bramante's Tempietto and Trajan's Markets, Castor built wire-frame models in Autocad as an armature for his rendered perspectives. The computer allows Castor's choices to be more "premeditated." Why did he study the Exchange with a mechanical pencil instead of a series of keystrokes? As Castor tells it, "Thoreau went to the woods to write deliberately." •



Daniel Castor, Berlage's Exchange, "Prodigal Son"



Daniel Castor, "Jellyfish Drawing" of Bramante's Tempietto



The Late Travel Sketches of Richard J. Neutra:

Seeing His World

Lauren Weiss Bricker, Ph.D.

See also Color Plates 1 through 3

If the recording of my world ever bordered on art, it was in the most casual manner, but a real human experience kept on oozing, dribbling, sprinkling, and sometimes freely flowing onto all kinds of accidental paper, whatever happened to be at hand. No spoken or slowly written word can quite express in the same way this past life, as lived in tiny fractions of time.

Life and Shape, 1962 1

In his autobiography *Life and Shape*, renowned Modernist architect Richard J. Neutra explains that travel sketches were his medium for capturing empathy or "in-feeling" with all he saw and encountered throughout his life. ² A sketchpad or sheaf of drawing paper were standard equipment on every trip Neutra took from his teenage years in Vienna to the end of his life. Through color, line, texture and shape, these graphic images depict many issues that informed Neutra's architecture: the dominant role of environment over human habitat, the need to create places for human interaction, and the design of objects as cultural signifiers.

In the College of Environmental Design, California State Polytechnic University, Pomona, we



left: Wetmansherde; above: Neutra sketching



Indus, Attock

are fortunate to own 106 Neutra travel sketches, made between the late 1940s and the end of the 1960s, just prior to his death in 1970. ³ The drawings were donated by architect Dion Neutra, son of Richard and Dione Neutra. A selection of the travel sketches was exhibited at Cal Poly Pomona in 1986, and later at the University of Southern California.

In the small catalog accompanying the Cal Poly exhibition, former Dean Marvin Malecha (who shares Neutra's passion for the travel sketch), noted that this medium "is far superior to the photograph when perception and understanding are the prime object...The designer can focus on those issues which are most important at the time or those which have made the biggest impression. Distortion, subtraction and even addition are essential to the travel sketch and they are equally important to the schematic design drawing." ⁴

According to Dion Neutra, the act of drawing was a visceral process for his father, through the use of the motor skills required for drawing he became physically engaged with the site. According to Dion Neutra, the creation of the travel sketches was a social act for Neutra. It was a chance to connect with people, as is evidenced in a photograph of Neutra surrounded by a group of Russian soldiers, and other onlookers. Dion Neutra believes the travel sketches functioned as a "memory peg" for Neutra, reminding him of what he'd seen and where he'd been.

The early travel sketches, the majority of which are housed in the Richard J. Neutra Collection, Department of Special Collections, UCLA,


exhibit the influence of Viennese artists Gustave Klimt and Egon Schiele on the young designer. The significance of drawing of all types was instilled in Neutra's professional education at the Imperial Institute of Technology in Vienna (which he entered in 1911), followed by his experience in the office of Berlin architect Erich Mendelsohn, the office of Frank Lloyd Wright, and later in collaboration with R.M. Schindler in Los Angeles.

While the majority of the Cal Poly Pomona travel sketches date from the late years of Neutra's life, the collection contains an earlier drawing of Mt. Palomar, in Southern California (1946). The mood of the drawing is somber: Neutra uses oil crayons to create a dense grouping of pine trees; with the edge of the crayon he crisply outlines boulders strewn in the foreground. As a foil to the sobriety of the scene, Neutra injects a small female figure in the lower left corner; she is tilting on one leg apparently buffeted by the wind that is blowing through the scene. The edges of the sheet are scorched, a reminder of the effect of the devastating fire that destroyed Neutra's first VDL Studio/Residence in the Silverlake district of Los Angeles in 1963.

The majority of the Cal Poly Pomona sketches were executed with pastels. Dion Neutra has noted that his father used larger-dimensioned sheets in his later years, which may contribute to the often-expansive character to his images. Neutra chose to depict historically significant sites, yet one never gets the sense of preciousness or self-conscious reverence for his subject. Instead, he extracts, edits, and emphasizes the aspects of the view that interest him.

The drawings tell us about how Neutra literally saw the world. In *Life and Shape* he explains that his that his left eye had a lens defect and was shortsighted, while his right eye was normal. Over time, the left eye became farsighted, and the other became more normal. He describes the effect of this condition on his visual perception:

Since most of the time I saw and worked with one eye, either the right one for minute sharp detail or the left for over-all composition, my mind similarly also swung back and forth—oscillated, so to speak, between an attempt at total comprehension, an integrated over-all view, and the minute perfectionism of near-sightedness. But I kept using each eye, one imaginatively and wholesale for over-all form, the other more observationally, for tiny, neat detail. ⁵



Obidos

Richard and Dione Neutra took photographic slides during their trips. ⁶ A comparison between a slide of site and Neutra's travel sketch reveals the way he "saw" a site. It is also reflective of the advantage of the sketch over the photograph as a medium for conveying his perception of a specific location. One such case is Cabo Espichel, in Sesimbra, Portugal on the coast south of Lisbon. The focus of the slide and Neutra's sketch, from the 1960s, is the Casa Agua, a small octagonal building within the 18th century Sanctuary of Our Lady of the Handle. In the photograph, the modest-sized building is surrounded by a grassy plain, with only a hint of its proximity to the coastal edge of the site. By contrast, the Neutra's sketch gave the building greater prominence by centering it in the picture, enlarging it and contrasting its solid polygonal form with a hint of blue sky and clouds and the shoreline. He also carefully renders the masonry wall framing the building's grass-covered entrance court, giving it much greater prominence than is evident in the more general view of the photograph. The sketch clearly

reveals those portions of the building and its context that interested him.

In his sketch titled "Wetmansherde" (1963), Neutra employs the traditional device of framing his subject through an arched opening. The scene is a grouping of vernacular. The key element of the drawing is a large tree that is planted near the base of the tower. The trunk and branches of the tree extend forward in the scene, its branches sending shock waves around the archway. Spatially the outline of the tree flattens the illusion of three-dimensional space created by the more traditional aspects of the composition. The eye of Neutra transformed the scene into one of considerable artistic interest.

Neutra's travels took him many points in Asia. A number of the travel sketches depict scenes in Thailand. His sketch of statue of the Buddha in Ayutthaya (1966) is the one the few interior drawings in the Cal Poly Pomona collection. The figure sits on a high throne, its green body contrasting with the golden throne and the deep red ceiling. Neutra



Polish Square

perspective so that he effectively fills the space near the back of the worship hall. Rather than treat the Buddha with extreme reverence, Neutra chose to capture the bemused expression of the figure as he looks down on his worshipers.

The breadth of Neutra's vision is clearly evident in his sketch of "Indus. Attock." (1968). Attock is a town located in the Punjab District of Pakistan. It is reported to have been along the route followed by Alexander the Great in 326 B.C. when he crossed the Hinduskush Mountains to capture the plains beyond the Indus River. The landscape embraces the town—the broad mountain range beyond is softly rendered, as is the vegetation and land—including an oxen in the foreground. The buildings are generalized, with a maroon edge defining an occasional corner or roof. The presence of the river is suggested. The overall effect is one of calmness, with the natural site conditions dominating the scene.

The Neutra travel sketches give us an insight into the great architect's world. Richard and Dione Neutra traveled the globe at a time when many Euro-

peans and Americans were much more provincial in the range of places they chose to visit. The travel sketches give us an insight into what Neutra saw, and how he saw it. As such, they give us a glimpse into the thinking and perception of the man, and perhaps his architecture. •

NOTES

- Richard Neutra. Life and Shape, New York: Appleton-Century-Crofts, 1962, 82.
- 2. Ibid.
- The Department of Special Collections, University of California, Los Angeles holds the earlier travel sketches, dating from the 1910s into the 1940s.
- Marvin J. Malecha. "Introduction. Understanding Architecture through Drawing." Richard Neutra Travel Sketches. The School of Environmental Design, Cal Poly University, Pomona, 20 October

 7 November 1986, n.p.
- 5. Life and Shape, 73-74
- The slides are housed in the Visual Resources Library, College of Environmental Design, California State Polytechnic University, Pomona.





Color Plate 1: Richard J. Neutra, Cabo Espichel





Color Plate 2: Richard J. Neutra, Bangkok Temple





Color Plate 3: Richard J. Neutra, Self Portrait



Color Plate 4: Perry Kulper, The Metaspheric Zoo, speculative proposal for the Prague Biennale




Color Plate 5: Perry Kulper, The Metaspheric Zoo detail, speculative proposal for the Prague Biennale




Color Plate 6: Laura Hartman, collage, mixed media on board.

The sensitive handling of color evident in this collage and those shown in Color Plate 7 informs the architectural work of her firm, Fernau & Hartman Architects, Berkeley, www.fernauhartman.com.





Color Plate 7: Laura Hartman, collage, mixed media on board.



LEE MANNING PHOTOGRAPHY

- Residential
 - Commercial
 - Real Estate



WWW.LEEMANNINGPHOTO.COM



See our other ads in this publication for more software and services.



AutoCAD° 2005

Is making waves!

- Smallest file size ever
- Network License borrowing for laptops
- CAD Standards
- Passwords and Digital Signatures for secure drawings
- Windows XP Certified
- Installs side-by-side with older Autodesk Software
- Training Available, call for options



AutoCAD®2005 go to www.cvis.com for an inside look at 2005

Whether you need Software or Training, CVIS IS YOUR SOURCE FOR AutoCAD

Call 1-800-511-8020 today to find out more about AutoCAD 2005



ACOUSTIC AND TECHNOLOGY CONSULTANTS

A Professional Service Firm Providing Acoustical Consulting and Technology System Design and Engineering for the Commercial, Corporate, Leisure, Public, Residential, and Retail Industries.

Three Locations to Serve You:


San Francisco, CA 510.886.7826 Los Angeles, CA 818.569.0234 Raleigh-Durham, NC 919.463.9995

For additional information on our firm visit our web site at: www.TA-Inc.com or send an email to: TA@TA-Inc.com

Thorburn Associates Inc is proud to be an AIA/CES Provider.

2005

AIACC AWARDS



- . Maybeck
- . Firm of the Year
- . Lifetime Achievement
- . Design
- . Savings By Design

2005 AIACC

Michael Franklin Ross, AIA Chair, 2005 AIACC Design Awards Committee

Five architects came together from around the country from different cities, different firms, different perspectives to judge 345 entries in this year's AIACC Design Awards.* Five architects with differing points of view, but with the same objective: to recognize the most thoughtful, the most artful, and the most well-resolved projects, both aesthetically and programmatically.

A public architect and LEED Accredited Professional, Deborah Weintraub, AIA, is the City Architect of Los Angeles. She oversees all municipal facilities design in California's largest, burgeoning metropolis. An educator, Professor and Dean Emeritus of Tulane University, Ron Filson, FAIA, also practices architecture in New Orleans. Earlier in his career, he was the Director of UIG at UCLA, teaching students to cross the bridge from the academic world to the realm of professional practice.

The three other jurors are principals in their own firms, and all three have served on the National AIA Design Awards jury. Mary Griffin, AIA, of Turnbull Griffin Haesloop in Berkeley, California, won an AIACC award last year for a private residence in Stinson Beach. Her firm is recognized for finely crafted wood architecture. Joseph Valerio, FAIA, is the lead designer of Valerio Dewalt Train in Chicago, Illinois. His work has been published in six recent books and a monograph by Rizzoli.

Peter Bohlin, FAIA, is a design partner of Bohlin Cywinski Jackson. They have five offices, in Wilkes Barre, Pittsburg, and Philadelphia, Pennsylvania; Berkeley, California; and Seattle, Washington. They have won national design awards for elegantly detailed houses and complex university laboratories.

These five diverse architects reviewed projects ranging from small additions and historic renovations to major urban complexes. Every project was judged on the same criteria: a clearly-stated, well-executed design idea that fulfilled its programmatic purpose and enhanced its environment. The results represent a broad spectrum of the best design work in California.

The jury spent two days reviewing over three hundred binders. Each juror initialed every binder, indicating they had personally reviewed it. At the end of the first day, there were still over sixty projects on the table. On the second day, jurors studied the binders and accompanying PowerPoint slides and ultimately concluded with the twenty-one winners; one Maybeck Award, one 25-Year Award, five Honor Awards, and fourteen Merit Awards.

The AIACC Maybeck Award is California's equivalent of the Gold Medal. This award honors an individual California AIA architect for outstanding achievement in producing consistently distinguished design. The 2005 jury selected Rob Wellington Quigley, FAIA. Ten years earlier, Rob's firm received the AIACC Firm Award. The jury was impressed not only with Quigley's consistently high level of design throughout his career, but also with his social consciousness. His work has served as a touchstone in the revitalization of San Diego. His leadership has been a catalyst in launching what has become known as the "San Diego School" of multi-family residential architecture. The jury observed that "his work has always been sustainable" and that his "design aesthetic is enabled by it, not hampered by it."

The 25-Year Award recognizes a California project completed twenty-five to fifty years ago that has retained its central form and character, with the architectural integrity of the project intact. The 2005 jury selected the Art Center College of Design in Pasadena, designed by the late Craig Ellwood and his partner Jim Tyler. The building is a timeless 864-foot long steel structure bridging a canyon, creating a dramatic entry sequence under the bridge. It is a tribute to the Art Center leadership that the unadorned beauty of this pure structure has been maintained and kept intact as a center for creative design.

Among the five Honor Awards and fourteen Merit Awards, what is most impressive is the wide range of award-winning work and the architects themselves. There were both familiar names and emerging talents, large firms and smaller partnerships. One of the benefits of the AIACC design awards program is to recognize well-resolved design projects regardless of size or budget.

Projects ranged in scope from the 2,000 square foot Sinclair Pavilion at the Art Center College of Design in Pasadena, by Hodgetts and Fung, to the more than 1,000,000 square foot Caltrans District 7 Headquarters Building in Los Angeles, by Thom Mayne, FAIA, of Morphosis.

The five Honor Awards alone included a broad range of scale, aesthetic approach and diverse design challenges. The 93,000 square foot Engineering Building at UC Santa Barbara, by Anshen + Allen Los Angeles, is a sophisticated, highly technical nanofabrication facility. Research labs require a rigorous design approach that respects the programmatic forces. The jury stated, "The more [we] looked at it, the more powerful it got."

An Honor Award was also bestowed upon a 10,000 square foot Mission District mixed-use complex by Kennerly Strong Architecture. The jury admired how the building, composed of three residential townhouses and street-level storefront commer-

cial, could make an architectural statement and respect its urban context on a difficult corner lot.

Two Honor Awards were given to single-family residences: one a masterful new building and one a sensitive, meticulous restoration. The Jackson Family Retreat in Big Sur, by Anne Fougeron, was cited by the jury as a "delicate house that hardly seems to touch the ground...detailed to perfection."

The other residence was R.M. Schindler's Elliot House, originally completed in 1930. I've been in this house many times. It was restored by Marmol Radziner and Associates to a level of design veracity not seen before. Major areas of work included restoration or rebuilding of significant structural damage and recreating Schindler's distinctive details.


The fifth honor award was given to the Swiss Government Plaza in Bern, Switzerland, by Lee & Mundwiler Architects of Santa Monica. This is essentially an urban design award for public space, a plaza that is a "prelude" to the Capitol Building. Through the careful selection of spare elements—stone, light and water—the plaza makes a quiet yet serene design statement.

What can we learn from these premiated projects and from the process itself? Design excellence finds itself in many disparate destinations. The design ideas of dedicated, tireless architects can make a difference in our lives in both public and private places. The awards program raises people's awareness of the value that design brings. It stimulates a dialogue about how we live and the choices we make. This jury consciously sought projects that were both aesthetically well-resolved and that made a clear statement. We hope these award-winning projects will stimulate your thinking and bring you what Vitruvius called "commodity, firmness and delight."

*The Executive Committee of the AIACC Board of Directors selects the Firm of the Year Award and Lifetime Achievement Award winners.

The **Savings By Design** Energy Efficiency Integration Design Awards, co-sponsored by the American Institute of Architects, California Council, annually recognizes professionals who achieve a rare combination of superlative design and creativity, environmental sensitivity, and innovative energy efficiency solutions.

The Savings By Design Awards were selected by a distinguished jury comprised of Nancy Clanton, PE, LC, IALD, President, Clanton & Associates, Boulder, Colorado; Katherine (Kate) Diamond, FAIA, Design Principal, RNL Design, Los Angeles; and Robert Noble, AIA, CEO and Design Principal of Tucker Sadler Group, San Diego, California.



San Diego Main Library Model

MAYBECK AWARD: Rob Wellington Quigley, FAIA

www.robquigley.com



San Diego Main Library Model

Rob Quigley, a native Californian, served as a Peace Corps architect in Chile after his graduation from the University of Utah in 1969. He founded his firm in San Diego in 1978 and opened a branch office in the Bay Area in 1994. The firm has ranged in size from five to fourteen people during that time, and greatly benefits from the experience of a core group of long-term, co-creative employees.

Starting with small, single-family residences in the 1970s, Mr. Quigley's pioneering work in passive solar design attracted worldwide media attention. As a design architect concerned about energy conservation, he has lectured locally, nationally, and internationally. In 1981, his Shukugawa Energy Demonstration House was built in Japan as a summation of American efforts in this field. Current sustainable efforts include the Leslie Shao-Ming Sun Field Station at Jasper Ridge Biological Preserve for Stanford University, which recently won the AIA Committee Award, and the West Valley Branch Library, San Jose's first LEED-certified civic building. The \$103 million San Diego New Main Library, now completing working drawings, will be California's largest LEED silver-rated building.

Mr. Quigley's mid-career work has focused on a pressing social issue: housing the "working poor." He worked with private





above: Beaumont Building


below left: Campaige Place


below: Gilman Mixed Use

developers and city officials to modify codes and rewrite ordinances to make privately financed, low-occupancy hotels. His ground-breaking Baltic Inn initiated a national trend in affordable, single-room occupancy hotels. The program resulted in the creation of over 2,000 units in San Diego and is emulated by cities from Atlanta to Seattle. The Baltic Inn was published in *Newsweek* magazine and received a Commendation from President Reagan. The Island Inn received a national AIA honor award and was selected as one of the best design processes involving the public, consultants, artists, and other designers.

The larger body of Mr. Quigley's work has focused on the unique possibilities of his particular region. Critics and editors from *Architectural Record* and *Progressive Architecture* to Esquire have applauded his efforts to define the more elusive aspects of the California culture and climate. •







Art Center College of Design, rendering by Carlos Diniz

25 YEAR AWARD:

Art Center College of Design Architect: Craig Ellwood Associates Design Associate: James Tyler Project Architect: Stephen Woolley addition, 1992, James Tyler Architecture




The Art Center College of Design, completed in 1977, stands as a landmark in the City of Pasadena. Although initially reluctant to allow its construction, the community has learned to love the unadorned steel structure spanning a canyon in the hills overlooking the Rose Bowl.


As the College's website describes it, "The 21,000-square-foot structure, situated on 175 wooded acres, provides space and facilities for the College's approximately 1,400 students, and its stark steel-and-glass design perfectly mirrors Art Center's modernist aesthetic. It is home to the College's undergraduate and graduate programs and includes film and photography labs, computer labs, and a professional recording studio among its many resources."

The entire campus is contained within the 144-foot by 864-foot building, which is designed with 48-foot square bays on the main level and 24-foot square bays on the lower level. There are no suspended ceilings except in the Bridge Wing, leaving the structural, electrical, and mechanical systems exposed, allowing the intrinsic nature of the building's construction to be expressed in a clear manner.

The Bridge Wing spans 192 feet across the canyon, supported









Care was taken in grading the steep site to preserve the character of the slopes and maintain the integrity of the ridges and canyons. The site is landscaped to restore the natural flora, augmented with groves of trees and shrubs native to Southern California. The Campus Drive approach curves in such a manner that the building becomes barely visible just before the drive passes under the Bridge Wing on its way to parking areas at the south end of the complex. All parking was planned to be out of sight from the school to provide clear views of nature.

The building—in which considerations of order, proportion, scale, materials, and color create a harmony of elements at all scales—stands in clear juxtaposition to the natural landscape, where students wander freely to sketch, reflect, and relax.


Note: see also the College's new Sinclaire Pavilion, by Hodgetts + Fung Design Associates, a 2005 Merit Award Winner, p. 72.



Main Level Plan



Lower Level Plan







FIRM OF THE YEAR AWARD: Morphosis

Los Angeles www.morphosis.net/morph.html

Thom Mayne and his Santa-Monica based firm, Morphosis, have been at the forefront of architectural innovation since the firm's founding in 1972. This highly collaborative group of forty professionals is committed to a critical practice, in which creative output engages contemporary discourse through architectural design, education, and writing. Morphosis' work ranges from designs for watches, teapots, and chairs to proposals for large-scale civic buildings to innovative urban design and planning schemes that reshape entire cities.


EDUCATION

Thom Mayne was among a small group of educators and students who founded the Southern California Institute of Architecture (SCI-Arc), whose humanistic, educational, and artistic values and ambitions have provided an important experimental venue for architectural and design professionals.

Throughout the history of the firm, Mayne's teaching and practice have fortified one another, as evidenced in the firm's recent commitment to LA Now. The first in a ground-breaking series of interdisciplinary, "wall-less classroom" initiatives, LA Now captures a "snapshot" of Los Angeles at the beginning of the 21st century. encouraging civic and business leaders, developers, architects, students, and the public to rethink the city and its future.



Rendering from the Wayne L. Morse U.S. Courthouse in Eugene, Oregon



Rendering from the Federal Building in San Francisco, CA

TECHNOLOGY, METHODOLOGY, PRODUCTION

In its early years, handmade drawings and models were important to the firm's production. While drawings and models remain paramount to its working process, cutting-edge technology has transformed the way in which Morphosis designs, collaborates, and produces buildings. A good example is the firm's use of Z Corporation's 3D Printer (www.zcorp.com), which allows the creation of physical models directly from 3D digital data, not only speeding the design process, but also helping to develop better solutions through frequent reviews and revisions.

THE PROFESSION AND THE BUILT ENVIRONMENT

The firm's early work in Los Angeles, such as the 2-4-6-8 House and Kate Mantillini's Restaurant, became emblems of the city's growing cultural sophistication. In the mid-1990s, Morphosis was awarded one of its first major public commissions, the Diamond Ranch High School in Pomona.


Over the past decade, the scale and complexity of the firm's work has continued to grow. The firm recently completed the \$171 Million Caltrans District 7 Headquarters in downtown Los Angeles and is now completing three major projects for the federal government's Design Excellence program: the San Francisco Federal Office Building, the Wayne L. Morse United

States Courthouse in Eugene, Oregon, and the NOAA Satellite Operation Control Center in Suitland, Maryland. These projects represent some of the most innovative and integrated solutions for sustainable building in the country.

Of these projects, architecture critic Nicolai Ourousoff has remarked, "[Mayne's] large-scale public projects serve as a valuable bridge between architecture's once-marginalized creative class and those who are often most distrustful of creative thought: government officials and developers. But even in designing expressions of institutional power, [Mayne] has been able to retain his underlying social agenda. His best work has a depth and complexity far beyond what we have come to expect in our public architecture. In an age of diminished expectations, this optimism may be its most radical feature." (Los Angeles Times July 25, 2004)

Mayne has also participated in planning projects around the world. Most recently, in May 2004, the firm was announced the winner of the international competition to design a 60-acre Olympic Village master plan for New York City's bid for the 2012 Olympics. •


See page 78 for the Merit Award: Caltrans District 7 Headquarters Building, Los Angeles



Psychiatric Inpatient Facility, UC Irvine Medical Center, 1992; Associated Architects: Moore Ruble Yudell Architects and Planners; Brockmeyer McDonnell Architects

FIRM OF THE YEAR AWARD: RATCLIFF Berkelev

www.ratcliffarch.com



above: New Computer Technology Center Laney Community College, Oakland, 2001

Founded by Walter H. Ratcliff, Jr., AIA, in 1906, RATCLIFF has shown a unique ability to survive through the Depression, two World Wars, and economic booms and busts. The axioms established by Walter and carried on by his son, Robert, his grandson, Christopher, and the firm today include:

- · to build is the ultimate act of optimism
- structures must have enduring value for the client and the community
- · architects are stewards of the environment

As a sole practitioner, Walter Ratcliff designed an estimated 300 buildings. RATCLIFF, the firm, is credited with an incredible range of projects, from single-family dwellings to retirement housing, kindergarten classrooms to college campuses, medical office buildings to full-service hospitals, and civic structures to commercial buildings.

As pioneers in the practice of healthcare architecture in the 1960s, RATCLIFF took the bold step of hiring a physician and nurse to educate the firm's architects about operational issues. Today, the firm employs a former hospital administrator to continue this legacy of in-house healthcare operations resources.

The firm uses process-mapping systems and up-to-the-minute

planning software to ascertain client needs and propose responsive approaches to project goals. The process often begins with project stakeholder "problem-seeking" workshops. Everyone from facilities manager to hospital volunteer gains a tangible role in developing durable solutions. Embracing this team approach and recognizing the benefits of establishing trusting relationships, the firm's planners have been known to recommend operational adjustments to a new client that eliminated the need for a new building.

When the architectural industry embraced technology as an essential business tool, members of the RATCLIFF team helped develop "Portfolio," a widely-used construction administration software system. The firm's Committee for Environmental Design Resources (CEDR) developed the Green MatrixTM, an Internet-based tool that provides a comprehensive, chronological application of sustainable design resources.

Long before sustainability became a buzzword, RATCLIFF was designing structures that were relevant to their era but were a strong investment in the future. "Buildings should grow old gracefully, that they be thought through all the way," said Walter Ratcliff. Long after the ground-breaking ceremony occurs, RATCLIFF clients call on the firm as a trusted advisor to assist in maintaining and renovating their facilities. For instance, the firm recently provided acoustical upgrades to Walter Ratcliff's award-winning Mills College Concert Hall to decrease the intrusion of noise from a nearby freeway and air traffic that Walter could not have envisioned in 1925.

Never a hierarchical firm with a single design aesthetic, RAT-CLIFF energizes the individual designer to contribute to a team effort. RATCLIFF mentors its members to grow not simply as designers, but as better people. As a way of returning to the firm's roots, each year the staff and their families are invited to a corporate retreat like no other. At Lone Rock Ranch in Mendocino County, a Ratcliff family treasure since 1926, the firm's extended family reconnects with its core value of respect for nature's beauty and returns to the office refreshed from a weekend of hiking, building sand castles at the beach, and relaxing at the rustic compound built of indigenous materials.

The firm's designers are impassioned about their craft and excited about the future. RATCLIFF remains and will continue to be a firm where architects can leverage great benefit for others and have fun doing so. And the optimism is infectious. •



above: Valley Life Sciences Building Renovation & Addition, UC Berkeley, 1995







above: Art Museum, Mills College, Oakland, 1920-30

2005 AIACC Design Awards




Stanford Shopping Center

John Field, FAIA

After college and graduate school at Yale, where Vincent Scully's architecture history classes convinced him to pursue his childhood fascination with architecture, John Field, FAIA, now Consulting Principal of Field Paoli, drove west, stopping in Chicago to see Harry Weese and in L.A. to see Craig Ellwood, neither of whom had work to offer. "I thought, well, I'm not really crazy about L.A. if I can't get a job with Ellwood. I'll go up and see a friend in San Francisco. I never meant to stay. I just thought I had all the freedom in the world, I should use it. And here I am."

"I went to see the architects whose work I liked, and every one of them said, 'Why don't you go back to Minnesota?' The joke in school had been, 'See you in Skidmore Owings and Merrill,' knowing there was very little work out there; I finally went to Skidmore. The fellow who interviewed me looked at my portfolio, with one Miesian design after another, and said, 'I'll tell you this, if I don't hire you, you're going to starve out here.'"

Following his stint at SOM—where Field learned to write specs, learned about project management, "why you wrote the documents you wrote, how you kept files organized so you can find something"—he opened a one-man office. "Periodically, I would get hungry and go back to work for somebody. One person I worked for was Henrik Bull. We were old friends. We were



Museum Thesis

also friendly with Woody Stockwell and Dan Volkman, who had an office together. One day over lunch, we realized that every client interviewed all four of us, so we got together."

Bull, Field, Stockwell, and Volkman set up a sabbatical program, so that each year one of the partners could take three months off to recharge their design batteries. "I had become more involved in projects that required community approval. I used to hate those meetings. I'm a patient man by nature, but I would just lose it. I realized that everybody in the room had a different picture in their head, because they didn't know how to talk about what they saw in their mind's eye. So I put in for a grant to make a documentary film. It was intended to give people a common language, both visual and verbal, to talk about why they liked things."

"The question was: why did people instinctively take their significant other's hand in some places and not in others? You watch in St. Mark's square, it is like magic, but it happens over and over: people walking in and discovering it. And I wanted to know why, because I figured if we knew why, then we could design it."

"We identified the sensory elements of spatial experience. We began with touch: your feet are touching the paving surface, it has a texture, and it varies. It varies if it's sloping up and if it's sloping down. We treated the urban space as rooms (and I think we were the first I'd ever seen do that). We dealt with the elements as space definers, what they were, what they could be, and how complicated they could be. The film, *Cities for People*, was on public TV in '74."

Field showed the film at Stanford, and the woman in charge of the shopping center called him and said, "You can make films about it, and you can lecture about it, can you design it?"

"Of course, I said, 'Yes,' and that's what led to doing the Stanford shopping center, a real career change. I had come to understand the complexity of spatial experiences and sequential spaces, and shopping center design was the easiest way to get to design two or three city blocks at a time. If you design as a city planner, you could wait thirty years before they ever built the whole thing, but if you design a shopping center, they build it tomorrow. Becoming a shopping center expert was a device, a way to get a chance to design a series of places."

"The thing that concerns me about architecture today is urban growth, which is gradually covering everything. Curiously, at

the same time, the profession has slipped into focusing on media figures—buildings can't just be background, we don't build background anymore. We don't build cities with accents; everything's an accent. That is not going to make cities we want to be in, ultimately."

"That's why I've been so interested in the increasing acceptance by developers of mixed use. I was telling shopping centers for years that they should put housing over the stores; they would just brush the idea aside. Today, they're beginning to do it. It's the coming of age of the suburbs into cities and towns with places."

For the complete interview with John Field, FAIA, visit the arcCA webpage at www.aiacc.org. For more on the work of Field Paoli, visit www.fieldpaoli.com.





top of page: Waldman House above: Boston Density drawing

Engineering Sciences Building, UC Santa Barbara

ARCHITECT:

Co Architects

(Formerly Anshen + Allen, Los Angeles)

www.coarchitects.com

CLIENT: The Regents of the University of California, Santa Barbara

LANDSCAPE ARCHITECT: Wallace Roberts & Todd, LLC, San Diego

ENGINEER: Arup, Los Angeles; Research Facilities Design, San Diego

OTHER CONSULTANTS: Applied Dynamics, Inc., Half Moon Bay; Carmen Nordsten Igonda, Los Angeles

GENERAL CONTRACTOR: The Austin Company, Irvine PHOTOGRAPHER: Assassi Productions, Santa Barbara

Size: 93,000 gross sq. ft.


Cost: \$27,000,000

This new engineering building, housing a nanofabrication research facility and flexible laboratories, defines the campus edge and establishes a pattern for further development. A freestanding pavilion, containing classrooms and meeting spaces, acts as a public porch, linking the building to the Campus Green and the coastal mountains to the north.
















Jackson Family Retreat, Big Sur

ARCHITECT:

Fougeron Architecture, San Francisco www.fougeron.com

CLIENT: (withheld at owner's request)

STRUCTURAL ENGINEER: Endres Ware Architects Engineers, Berkeley

OTHER CONSULTANTS: Hardman Glazing, San Leandro
GENERAL CONTRACTOR: Thomas George Construction,
Carmel


PHOTOGRAPHER: Richard Barnes, San Francisco

Size: 2,500 sq. ft. Cost: (withheld)


Acknowledging the ecologically fragile nature of its site, this two-bedroom house sits lightly on the land. Its four principal volumes, clad in different materials—standing seam copper, Alaskan yellow cedar, glass and steel, and integrally colored stucco—interweave to create visual and spatial complexity.















Mission District Mixed-Use, San Francisco

ARCHITECT:

Kennerly Strong Architecture, San Francisco CONSULTING ARCHITECT: Winder Architects, San Francisco

CLIENT: Werner Associates, Mill Valley

STRUCTURAL ENGINEER: Santos & Urrutia, Inc., San Francisco

ACOUSTICAL ENGINEER: Shen, Milsom & Wilke, Inc, San Francisco

GENERAL CONTRACTOR: Werner Associates, Mill Valley PHOTOGRAPHER: Matthew Millman, San Francisco


Size: 10,000 sq. ft. Cost: \$2.1 million An innovative corner building evinces two personas, public and private. A retail storefront wraps the corner, maximizing street activity. Internally, the design up-ends the horizontal, front-to-back relationship of the typical row house to create vertical homes that flow from the formal entry court to roof gardens with panoramic views.

















SECOND FLOOR PLAN

Federal Government Plaza (Bundesplatz), Bern, Switzerland

ARCHITECT:

Lee + Mundwiler Architects, Santa Monica www.lm-arch.com ASSOCIATE: Stauffenegger + Stutz, Basel, Switzerland CLIENT: Swiss Government/City of Bern, Switzerland PHOTOGRAPHER: Ruedi Walti, Basel, Switzerland

Size: 100,000 sq. ft. **Cost:** \$6.775 million


The arranged emptiness of the Federal Government Plaza, composed of stone, light, and water, implies no political doctrine and refers to no social strata. It provides a truly neutral space for all, accommodating a variety of functions from weekly markets and concerts to national celebrations and political demonstrations.

















Elliot House Restoration, Los Angeles

ARCHITECT:

Marmol Radziner and Associates, Los Angeles www.marmol-radziner.com **CLIENT:** Cameron Silver, Los Angeles

STRUCTURAL ENGINEER: Niver Engineering, Los Angeles


GENERAL CONTRACTOR: Marmol Radziner and Associates, Los Angeles

PHOTOGRAPHERS: Benny Chan, Los Angeles; Tim Street-Porter, Hollywood; William Claxton, Los Angeles


Size: 2,100 sq. ft. Cost: (withheld)

The architects approached the restoration of R.M. Schindler's Elliot House of 1930 with the goal of maintaining the integrity of the master's vision while acknowledging the realities of contemporary living. Working from original plans and photographs, the firm's in-house shop recreated cabinetry and furnishings from Schindler's original designs.

















Conservatory of Flowers Rehabilitation, San Francisco

ARCHITECT:

Architectural Resources Group, San Francisco www.argsf.com/home_anim.shtml DESIGN ARCHITECT: The Portico Group, Seattle, Washington

OUTBUILDING ARCHITECT: baker vilar architects, San Francisco

CLIENTS: Department of Recreation and Parks, San Francisco; Friends of Recreation and Parks, San Francisco; San Francisco Park Trust; Project Management & Construction Management, Department of Public Works, San Francisco

STRUCTURAL ENGINEER: Tennebaum-Manheim Engineers, San Francisco

MECHANICAL ENGINEER: Mechanical Design Studio, Walnut Creek, San Francisco

ELECTRICAL ENGINEER: POLAinc, San Francisco

CIVIL ENGINEER: Bennet Consulting Group, San Francisco


LIGHTING DESIGNER: Horton Lees Brogden Lighting Design, San Francisco

EXHIBIT DESIGNER: Portico Group, Seattle, Washington

GENERAL CONTRACTOR: ISEC, Inc. and Troy's Contracting, Davis

PHOTOGRAPHER: David Wakely Photography, San Francisco

A series of storms in December 1995 severely damaged the Conservatory of Flowers in Golden Gate Park, California's oldest public greenhouse, forcing its closure. The restoration involved relocation of the plant collection; a temporary, in situ greenhouse for immovable specimens; new interpretive exhibits; and structural and mechanical upgrades.









Camino Nuevo Charter Academy Elementary School, Los Angeles (Phase One)

ARCHITECT:

Daly, Genik Architects, Los Angeles www.dalygenik.com CLIENT: Pueblo Nuevo Enterprises, Los Angeles

LANDSCAPE ARCHITECT: Mia Lehrer + Associates, Los Angeles

STRUCTURAL ENGINEER: William Koh & Associates Inc., Los Angeles


MECHANICAL ENGINEER: Retrofit Service Co., Inc., Rancho Cucamonga

ELECTRICAL ENGINEER: Briggs Electric, Inc., Irvine
PLUMBING ENGINEER: Elite Plumbing, Inc., Santa Ana
GENERAL CONTRACTOR: Miller Company, Irvine

PHOTOGRAPHER: Tom Bonner, Venice

Size: 21,000 sq. ft. **Cost:** \$1.7 million

By reusing and renovating a mini-mall and parking lot, a familiar type of commercial building is transformed into an inviting elementary school, focused around an enclosed courtyard. The building creates a strong identity for the school while seamlessly integrating into the urban neighborhood by maintaining a low building height and using everyday materials.











Sinclaire Pavilion, Pasadena

ARCHITECT:

Hodgetts + Fung Design Associates, Culver City www.hplusf.com CLIENT: Art Center College of Design, Pasadena LANDSCAPE ARCHITECT: LRM-LTD, Culver City

STRUCTURAL ENGINEER: William Koh & Associates Inc., Los Angeles


CIVIL ENGINEER: KPFF Consulting Engineers, Santa Monica

GENERAL CONTRACTOR: Matt Construction, Santa Fe Springs

PHOTOGRAPHERS: Craig Hodgetts, Culver City; Hsin-Ming Fung, Culver City; Marvin Rand, Venice

Size: 2,000 sq. ft. **Cost:** \$750,000

Situated on a knoll overlooking the clipped green lawn surrounding Craig Ellwood's elegant Miesian extrusion, this new student lounge is the only other free-standing structure on the sixty-acre site. It celebrates the virtues of mechanics through human-powered elements that pivot, swivel, and glide, emphasizing the roots of the school's industrial design curriculum.











Sylmar Branch Los Angeles Library, Sylmar

ARCHITECT:

Hodgetts + Fung Design Associates, Culver City www.hplusf.com CLIENT: Los Angeles Public Library

LANDSCAPE ARCHITECT: Katherine Spitz Associates Inc., Marina del Ray

STRUCTURAL ENGINEER: Englekirk & Sabol Consulting Structural Engineers, Inc., Los Angeles

ELECTRICAL ENGINEER: Byrne & Associates, Reseda


GENERAL CONTRACTOR: Royal Construction Corporation, Arcadia


PHOTOGRAPHER: Craig Hodgetts, Culver City; Marvin Rand, Venice

Size: 12,000 sq. ft. **Cost:** \$3.6 million

In an outlying district of metropolitan Los Angeles, hard against the San Gabriel Mountains, a casually creased roof rests on irregularly spaced columns, setting up a lively rhythm and creating a civic building that is unexpectedly light and unself-conscious. Multi-hued and heavily textured, the roof echoes the eclectic montage of neighboring structures.









Photography Studio & Workshop, Petaluma

ARCHITECT:

Kennerly-Bowen Architecture, San Francisco CLIENT: Thomas Heinser & Madeleine Corson,

STRUCTURAL ENGINEER: Level Structural Engineering, Sebastopol

GEOTECHNICAL ENGINEER: Herzog Geotechnical, Mill Valley


MECHANICAL ENGINEER: Peter Alspach, San Francisco

GENERAL CONTRACTOR: Fairweather & Associates, Sebastopol


PHOTOGRAPHER: Thomas Heinser

Size: 2,200 sq. ft. **Cost:** \$330,000

Located on agricultural land in western Marin County, a gabled basilica echoes the cross-sectional properties of an enchanting but irreparable barn, which it replaced. It advances the expressive and functional possibilities of agricultural buildings, transforming a pre-engineered metal building system through refinement of its proportions and elaboration of its enclosure system.









Nissan Styling Studio, Farmington Hills, Michigan

ARCHITECT:

Luce et Studio, San Diego www.lucestudio.com

ASSOCIATE ARCHITECT: Albert Kahn Associates, Inc., Detroit, Michigan

CLIENT: Nissan Design America, Inc., La Jolla

LANDSCAPE ARCHITECT: Claude Cormier Architectes Paysagistes Inc., Montreal

STRUCTURAL ENGINEER: Wallace Engineering, Kansas City, Missouri

GENERAL CONTRACTOR: Turner Construction Company, Detroit, Michigan

OTHER CONSULTANTS: A. Zahner Co. Architectural Metals, Kansas City, Missouri

PHOTOGRAPHER: Paúl Rivera/Archphoto, New York, New York

Size: 45,000 sq. ft. Cost: (withheld) A new studio wing centers around a generous loggia, an active space that changes as staff communicate through visual image, modeling, and prototyping, forming a public landscape of the design process. Its main modeling studio looks out onto "The Egg," the studio's signature outdoor viewing courtyard.














Joseph A. Steger Student Life Center, University of Cincinnati, Cincinnati, Ohio

ARCHITECT:

Moore Ruble Yudell Architects & Planners, Santa Monica www.moorerubleyudell.com ASSOCIATE ARCHITECT: glaserworks, Cincinnati, Ohio

CLIENT: University of Cincinnati, Cincinnati, Ohio

LANDSCAPE ARCHITECT: Hargreaves Associates, San Francisco

STRUCTURAL ENGINEER: Arup, Los Angeles with THP Limited, Cincinnati, Ohio

MECHANICAL/ELECTRICAL/PLUMBING ENGINEER: Arup, Los Angeles, with Heapy Engineering, Dayton, Ohio

ENVIRONMENTAL GRAPHIC DESIGNER: Kolar Design Associates, Cincinnati, Ohio

GENERAL CONTRACTOR: Dugan & Meyers Construction, Cincinnati, Ohio

PHOTOGRAPHER: Alan Karchmer, Washington, DC

Size: 65,000 sq. ft. new construction; 35,000 sq. ft. renovation

Cost: \$26.2 million

A dense mix of academic, social, and retail uses establishes a new spine for campus activity. From the window bay for one or two, to a quiet mews terrace, to the large enclosure of atrium or sweep of arcade, the inhabitant engages in dynamic interaction with the building and its setting.









Dr. Theodore T. Alexander Jr. Science Center School, Los Angeles

ARCHITECT:

Morphosis / Thom Mayne, Santa Monica www.morphosis.net/morph.html

CLIENT: Los Angeles Unified School District

LANDSCAPE ARCHITECT: Katherine Spitz Associates Inc., Marina del Rey

STRUCTURAL ENGINEER: Englekirk & Sabol Consulting Structural Engineers, Inc., Los Angeles; Don C. Gilmore Associates, Los Angeles

GENERAL CONTRACTOR: Bernards Brothers, San Fernando

PHOTOGRAPHERS: Benny Chan, Santa Monica; Gary Leonard, Los Angeles

Size: 196,000 gross square feet


Cost: (withheld)

Renovation of an existing armory creates a hybrid campus of primary education and scholastic research, complementing the greater USC-Exposition Park Museum and Education campus and establishing a community foothold in the heart of South Central LA. New structures are introduced into the site through the subtle merging of building and ground.











Caltrans District 7 Headquarters Building, Los Angeles

ARCHITECT:

Morphosis / Thom Mayne, Santa Monica www.morphosis.net/morph.html

CLIENT: State of California, Department of General Services, Los Angeles

LANDSCAPE ARCHITECT: Campbell & Campbell, Santa Monica


STRUCTURAL ENGINEER: John A. Martin Associates, Inc., Los Angeles

GENERAL CONTRACTOR: Clark Construction, Los Angeles


PHOTOGRAPHER: Roland Halbe, Stuttgart, Germany

Openness, interplay, and sustainability characterize this office building, with its outdoor lobby enlivened by a neon and argon light installation. Perforated aluminum panels open and close automatically, providing surface variety, sun shading, and ever-changing views; and photovoltaic panels on the building's south face provide 5% of the facility's electricity needs.









Orange Grove, West Hollywood

ARCHITECT:

Pugh + Scarpa www.pugh-scarpa.com/indexmain.html CLIENT: Urban Environments, Inc., Los Angeles

STRUCTURAL ENGINEER: Oxford Engineering Company, Woodland Hills

CIVIL ENGINEER:

GENERAL CONTRACTOR: Becker General Contractors, Inc., Los Angeles

PHOTOGRAPHER: Marvin Rand, Venice

Located in a neighborhood characterized by 1950s "dingbat" apartment buildings, this ensemble of five townhomes provides large, simple interior spaces in an idiom of strongly defined shapes rendered in industrial materials. Unlike neighboring structures, the building uses large balconies to create a strong relationship with the street.











Solar Umbrella, Venice

OWNER:

Angela Brooks, AIA, & Lawrence Scarpa, AIA, of Pugh + Scarpa, Santa Monica www.pugh-scarpa.com/indexmain.html CLIENT: Angela Brooks, AIA, & Lawrence Scarpa, AIA, Venice

LANDSCAPE ARCHITECT: SQLA Inc., Los Angeles

INTERIOR DESIGN: Angela Brooks, AIA, & Lawrence Scarpa, AIA, Venice

STRUCTURAL AND CIVIL ENGINEER: Gwynne Pugh, P.E., AIA

SUSTAINABILITY ENGINEER: John Ingersoll, P.E., Ph.D.


SOLAR DESIGN AND ENGINEERING: John Ingersoll, P.E., Ph.D.

GENERAL CONTRACTOR: Above Board Construction, West Los Angeles

PHOTOGRAPHER: Marvin Rand, Venice

Inspired by Paul Rudolph's Umbrella House and Heyward Apartments of 1953, the Solar Umbrella provides a contemporary reinvention of the solar canopy, a formal strategy that provides thermal protection in climates with intense exposures. Passive and active solar design strategies render the residence 100% independent from the grid.














3rd & Benton / 7th & Grandview Primary Centers, Los Angeles

ARCHITECT:

Rios Clementi Hale Studios, Los Angeles www.rchstudios.com **CLIENT:** Los Angeles Unified School District

LANDSCAPE ARCHITECT: Rios Clementi Hale Studios

STRUCTURAL ENGINEER: Taylor & Gaines, Encino

MECHANICAL/PLUMBING ENGINEER: John Denton & Associates, La Cañada

ELECTRICAL ENGINEER: VIRTEC Engineering,

Agoura Hills

CIVIL ENGINEER: William Rose & Associates,

Santa Clarita


COST ESTIMATOR: Davis Langdon, Santa Monica

GENERAL CONTRACTOR: Pinner Construction Company, Inc., Anaheim

PHOTOGRAPHERS: top left, Johnathan Dewdney; all others, Rios Clementi Hale Studios

Size: 14,000 sq. ft. (average)
Cost: \$3.2 million (average)

A prototypical set of buildings and site planning strategies are realized in two new Primary Centers—self-sufficient schools for kindergarten through 2nd grade. An inverted roof allows clerestory lighting for the classroom prototype, based on the prescribed "relocatable" classroom unit. Outdoor classrooms connect to a large, colorful "carpet" of sports and game courts.









House on Blue Jay Way, Los Angeles

ARCHITECT:

SPF:a, Los Angeles www.spfa.com

CLIENT: Jeff Bueth, Hermosa Beach

STRUCTURAL ENGINEER: Henry Guzman, South El Monte


GENERAL CONTRACTOR: William Kent Development Inc., Winnetka


PHOTOGRAPHER: John Edward Linden, Woodland Hills

A four-level spec home, perched on a steep grade overlooking the Los Angeles basin, represents a beautiful client-architect partnership. The client, a designer by trade, designed many of the furnishings for the residence and selected others to best showcase the home's inviting architecture.









Hay Barn and Stable, Somis

CLIENT: Steve Sharpe, Somis

STRUCTURAL ENGINEER: Castlebrook Barns, Fontana
GENERAL CONTRACTOR: Castlebrook Barns, Fontana
PHOTOGRAPHER: John Edward Linden, Woodland Hills


Organized around a 12 foot by 12 foot steel structural system, this barn and stable uses hay bales themselves as a rough, constantly changing cladding on a sleek, unchanging frame. Horses eat the hay, sometimes right off the building.

DESIGN ARCHITECT:

SPF:a, Los Angeles www.spfa.com









Energy Efficiency

Integration Awards

2005 Winners Set New Standards in Energy-Efficient Design

For their achievement in combining exceptional design, environmental sensitivity, and energy efficiency, eight California non-residential projects received awards of recognition from the 2005 Savings By Design Energy Efficiency Integration Awards program.

Every year, the recognition program, sponsored by Pacific Gas and Electric Company, San Diego Gas & Electric. Southern California Edison, Southern California Gas Company, and The American Institute of Architects, California Council (AIACC), recognizes the extra energy it takes to successfully integrate architectural excellence and energy efficiency.

This year, two exceptional projects rose to the top to receive Awards of Honor. Two other outstanding projects received Awards of Merit, and four noteworthy projects received special citations.

"Between the record number of entries and the general evolution of expertise in energy-efficient design, this year's competition was intense," commented Charles Angyal, FAIA, Chief Architect at San Diego Gas & Electric. "But the deserving winners still rose solidly to the top, setting new standards for the design community."


The jurors cited the projects' masterful use of design to create beautiful, high-quality working and learning environments that seamlessly integrate energy efficiency.

AWARD OF HONOR:

"Casa Nueva" Santa Barbara County Office Building Santa Barbara









ARCHITECT: Blackbird Architects, Inc.

OWNER: Santa Barbara County

DESIGN TEAM: Mechanical Engineering Consultants, Inc.

JMPF

Van Atta Associates, Inc.

PHOTOGRAPHY: William B. Dewey

Resting on an airy rise on a campus of county buildings, this model office building exemplifies creative space, innovative design, and green building practices. The vibrant workspaces and open floor plan in the 28,000 square-foot building encourage the 105 occupants to interact with their environments with user-controlled daylighting and operable windows.


A trellis of simple yet dramatic shade fabric and flowering wisteria shields the south and west sides from seasonal heat gain. The courtyard, which includes amenities such as outdoor workstations and occupiable artwork, provides spaces to work, collaborate, and recreate, while respecting the environment through sustainable materials, energy- efficient design, and native landscaping.

"This project can establish a precedent as a standard for technology, aesthetics, and honesty in environmental design," the jurors affirmed. They applauded the building's budget-conscious simplicity as a prototype for creating a vibrant work environment that respects the environment, as well as its inhabitants. Even though the facility is basically a "simple stucco box," jurors pointed out that the passive energy efficiency solutions and abundant detailing elevate the design.

"This is the epitome of integration. The vegetation, landscape, shading devices, and mechanical system all work together wonderfully," jurors commented. "It's the type of environment in which anybody would love to work."

AWARD OF HONOR: Global Ecology Research Center Stanford









ARCHITECT: EHDD Architecture

OWNER: Carnegie Institute of Washington

DESIGN TEAM: Rumsey Engineers, Inc., Engineering Enterprise, JS Nolan & Associates, Loisos + Ubbelohde

PHOTOGRAPHY: Peter Aaron

In keeping with the mission of the Global Ecology Research Center, this research facility drastically reduces carbon impacts while providing laboratory and research spaces that meet the strictest standards of comfort and performance. Strategies such as natural daylighting and radiant heating/cooling minimize energy use and maximize occupant thermal, acoustic, and visual comfort.


Among its innovations is a tower assisted by a windcatcher top that evaporatively creates a cool breeze in the lobby area. The facility also features a combination of radiation and evaporative cooling that produces chilled water via a rooftop-mounted spray system that operates at night.


Jurors praised the building's refined details, use of natural materials and daylight, and inventive integration of building form with passive ventilation and lighting. Calling the mechanical system "gutsy," from the windcatcher to the nighttime spray on the roof, the jurors felt that the building could function as a learning environment for designing other mechanical systems.

"This project captures the best sense of sustainable design: that it is not an 'either/or' between environment and humanity, it's a 'both' by inventing new design strategies. When we harness creativity, we can do all of the above."

AWARD OF MERIT: The Audubon Center at Debs Park Los Angeles







ARCHITECT: EHDD Architecture

OWNER: The Audubon Center at Debs Park

DESIGN TEAM: IBE Consulting Engineers, Kanwar Associates
Soltierra LLC, CTG Energetics, Inc.


PHOTOGRAPHY: Cesar Rubio

This nature center, sited in an ecologically degraded native habitat on the edge of an under-utilized public park two miles from downtown Los Angeles, is designed to bring children outdoors into nature. The project includes a 6,747-square-foot building with a multipurpose class/meeting room, offices, kitchen storage, library and reception; a children's garden; and interpretative trails. The building is 100 percent solar-powered and produces more energy than it consumes.

The project showed sensitivity to its environment by restoring the native landscape, utilizing passive energy-conservation strategies, incorporating sustainable materials, and including on-site stormwater retention and on-site wastewater treatment and dispersal systems.


"Beyond the ambition of being a Platinum LEED™-rated building that is independent of the power grid," the jurors remarked, "this project demonstrates a strong commitment to the environment." They particularly appreciated the constructed environment of the courtyard leading to the natural environment of the park, and the idea of connecting school children to nature in the heart of Los Angeles. "The innovation of the photovoltaic grid is extraordinary, and the whole project has a sense of calm, serenity, and rightness with the environment."

AWARD OF MERIT: Cesar Chavez Elementary School Long Beach









ARCHITECT: LPA, Inc.

OWNER: Long Beach Unified School District

DESIGN TEAM: Fundament and Associates

PHOTOGRAPHY: Cris Costea

Located in a once blighted downtown redevelopment area, this joint-use elementary school and community health clinic was designed to become a sustainable learning laboratory and a catalyst for redevelopment and community pride in the neighborhood. In addition to classrooms and the health center, it includes a joint-use gymnasium, hard courts, and a lunch shelter in 75,000-square feet of enclosed space on a restrictive 2.5 acres. Natural daylight illuminates 90 percent of the interior spaces and natural ventilation cools 75 percent of the indoors.

"The ability to integrate innovative environmental technologies into a well-sculpted building is a tough job and done extremely well in this project," declared the jurors. They complimented the building's use of color, its relationship to the open space, and its simple, integrated, and repeatable design. The innovative project solved many sustainable issues in spite of the challenge of severe budget constraints.

"It's the kind of long-term reality that we need in order to build wonder-filled places for children," the jurors concluded, "not just when they're in school but in all environments created for them."

CITATION:
Natural Resources Defense Council
San Francisco







ARCHITECT: Leddy Maytum Stacy Architects

OWNER: Natural Resources Defense Council

DESIGN TEAM: Rumsey Engineers, Inc., Architectural Lighting Design, Engineering Enterprise

PHOTOGRAPHY: Cesar Rubio


Sited in a landmark 22-story downtown office building constructed in 1927, this office renovation project demonstrates that energy-efficient, environmentally responsible workplaces are cost-effective and beneficial for businesses of all types. The 19,700-square feet of space in two stories includes private offices, open work areas, conference rooms, and a law library. The design enhanced the building's existing features—operable windows, steam radiant heat, narrow floor plates, and abundant daylight—to create expanded access to natural light and views and improved air quality to minimize energy use and increase comfort. In addition, the project used recycled/ renewable/nontoxic materials and implemented aggressive water management and indoor air quality programs during construction.

"The design approach following through on such a wide array of sustainable technologies in a small space is outstanding," the jurors enthused. "The lack of waste in the new elements should be a valuable precedent for designers doing historic renovations in existing buildings." They particularly praised the space's quality of light, even in the most interior areas, the demonstration of recycled and reclaimed materials, and the extraordinarily refined detailing.

CITATION:

Morgan Hill Aquatics Center Morgan Hill







ARCHITECT: ELS Architecture and Urban Design

OWNER: City of Morgan Hill

DESIGN TEAM: Rumsey Engineers, Inc., IDEAS, Rowley International, Inc.,

Donald Ballanti

PHOTOGRAPHY: David Wakely


This recreational and competitive aquatic facility integrates environmentally sensitive design, energy saving features, and community programming to create an outdoor social center with four pools and low-maintenance support buildings on 8.5 acres. The building features solar panels, natural ventilation, and abundant daylighting, but its most innovative energy-saving feature is the use of fabric windscreens that reduce heat loss from evaporation due to wind. In addition to reducing pool heating costs by 40 percent, the windscreens allow for separation between competitive and leisure aquatics programs while allowing free flow between them.

This project's inventive and effective use of windscreening to profoundly affect energy efficiency impressed the jurors. According to jurors, this application solved multiple engineering challenges. They also cited the integration of natural materials with a soft and refined overall aesthetic, and the appropriate relationship of shape and technology in the use of a shed roof for future solar collectors. Jurors praised the successful indoor-outdoor relationship between various spaces and their functions.

CITATION: Eastern Sierra Inter-Agency Visitors Center Lone Pine







ARCHITECT: Marcy Wong & Donn Logan Architects

OWNER: USDA Forest Service, lead agency

DESIGN TEAM: Mechanical Design Studio, SCE Engineers,
Green Building Services, Lawrence Berkeley Laboratory

PHOTOGRAPHY: Bill Hustace

Sited on 12 acres in a picturesque high-desert valley near Mount Whitney, this 6,000-square-foot facility with a north-south orientation combines exhibit space, a bookstore, inventory preparation and storage areas, pubic restrooms, office area, and foyer with information and permit counters. In designing this energy-efficient project, the architects integrated lightshelves and sun shades, a ground source heat pump, high-albedo roofing, and fenestration that minimizes heat gain and loss and maximizes views of Mt Whitney.

The environmentally sensitive project restored the site to its native alkaline meadow and created a demonstration native plant garden. Educational displays highlight the history of the region, its environment, and resource issues.

The jurors appreciated the project's inventive geothermal HVAC system. They felt that the white roof was an effective energy efficiency strategy that provides an aesthetic appropriate to the site and the mountains. Jurors viewed the building as a contextually appropriate, simple shed solution that integrates a variety of energy efficiency and sustainability choices.

CITATION FOR CLASSROOM DESIGN: Solana Pacific Elementary School San Diego







ARCHITECT: HMC Architects

OWNER: Solana Beach School District

DESIGN TEAM: Merrick & Associates, Johnson Consulting Engineers

PHOTOGRAPHY:

Interior photo: Hewitt Garrison Architectural Photography

Other photos: John Durant

The design of this 80,000-square-foot school emerged from the unique coastal location of the site, program needs, and the physical context. The school, which serves 550 kindergarten through grade six students, includes a fine arts performance space, administrative offices, a reading room, library, computer lab, special rooms for music, science and art, and a lunch area. It is sited to take advantage of on-shore prevailing breezes for natural passive cooling. The project also makes great strides in capturing daylight, maximizing occupant thermal comfort and indoor air quality and in it its use of recycled materials.

The classrooms in this project particularly impressed the jurors. "The daylighting design with its clerestories and views is spectacular," they remarked. "With their inside and outside fun spaces and translucent shading devices, the classrooms are well-designed to create great learning environments."

Savings By Design

Provides Design Assistance and Financial Incentives

It's no accident

that buildings are energy-efficient;

high performance buildings

happen by design.

Savings By Design, a program that encourages high-performance design and construction, offers design assistance and financial incentives to architects and building owners who strive to integrate energy efficiency into their non-residential, new construction projects.

The design assistance and financial incentives are immediate, but the added benefits of an energy efficient facility are ongoing: lower operating expenses and increased property value, occupant comfort, and productivity.

Design assistance is available to help architects design the most efficient buildings possible by providing informed recommendations and analysis.

Design teams who meet ambitious energy efficiency targets can earn up to \$50,000 in incentives. To qualify, teams must contact a Savings By Design representative early in the design process, incorporate integrated design, and exceed program baselines by 15 percent.

When building owners use a whole building, integrated design approach and exceed program baselines by 10 percent, they are eligible to receive up to \$150,000 in incentives. Owners using a systems approach may receive up to \$75,000.

Savings By Design is funded by California utility customers under the auspices of the Public Utilities Commission and sponsored by Pacific Gas and Electric Company, San Diego Gas & Electric, Southern California Edison, and Southern California Gas Company. For more information about Savings By Design or the Savings By Design Energy Efficiency Integration Awards, which recognizes successful high performance buildings, visit www.savingsbydesign.com. Projects must be located within the service territories of: Pacific Gas and Electric Company, San Diego Gas & Electric, Southern California Edison Company, and Southern California Gas Company.















Subscription Information

Send check or money order & subscription form to:

c/o AIA California Council 1303 J Street, #200 Sacramento, CA 95814

Name:	_Address:	
City	_State, Zip:	
Phone:	_Fax:	
Single Copies: \$6 for AIA members; \$9 non-me	embers	arcca
Subscription Prices (four issues per year): \$24 AIA members; \$15 students; \$34 non-members; U.S.: \$38 Canada; \$42 foreign. Note: AIACC members receive one free subscription of arcCA as a benefit of their dues.		Drawn .
Make check or money orders payable to: AIA C	alifornia Council	* Out
Or to pay by credit card, please check one:	ISA 🔲 MC 🔲	n U
Account Number:		
Expiration Date:		drawing for architecture
Signature:	<u></u>	Ais, Nartmann, Sniper, Laurier, Nortm



The HVAC System Is.

The "Ouiet Climate" is Bard's newest and quietest Wall-Mount HVAC system. In fact, it's 50% quieter than previous models. With noise levels this low your teachers won't need to turn the system off to conduct lessons.





Call toll-free or visit our website today and learn how you can improve classroom ventilation and comfort with Bard.

Geary Pacific Supply Phone: 800-444-3279 ext. 122 • Fax: 714-279-2940 www.gearypacific.com





See our other ads in this publication for more software and services.

Are you still creating architectural designs in AutoCAD°?

Architectural Desktop®2005 was built for YOU!



- AutoCAD 2005 Software built in
- VIZ4 photorealistic rendering engine included
- Single Click Object Insertion for repetitive objects like doors and windows
- Intelligent Objects that behave like their real world counterparts
- · Linked plans, sections, and elevations from a single model
- options

Call CVIS today at 1-800-511-8020 to find out more about • Training Available, call for this NEW release, or visit www.cvis.com

WHEN IT COMES TO SCHOOLS, WE'VE DONE OUR HOMEWORK.



Long Elementary Terrell, TX Claycomb Associates





Empire College Santa Rosa, CA Glass Architects

complete exterior package, including curtain walls, entrances, storefronts, windows, skylights and translucent panel systems, The Vistawall Group has supplied innovative school and university construction projects across the country. When you plan your next educational project, go with a single-source supplier that already has done its homework.

Distinguished by our ability to offer a

For more information, call us today at 800/327-1411, or visit www.vistawall.com.

And Group

And Dojects across

In your next


And A single
In a single-

The Vistawall Group A BlueScope Steel Company

Mary Gates Hall University of Washington Seattle, WA

windows & doors






LIKE THIS, YOU MAY NOT EVEN NOTICE THE REST OF THE HOME.

designed to be true to any architectural style. You supply the vision. We'll supply the rest. Visit our Web site at www.architecturaltraditions.com



Architectural Traditions

OLD WORLD CHARM **COMES NATURAL!**



Nestled near the Catalina Mountains of Tucson, Arizona, Architectural Traditions is the only company of its kind...allowing the architect, builder, designer and/or homeowner complete control...ensuring that the windows, doors, hardware, wood flooring and cabinet fronts are built with a consistent look and quality that only a single-source supplier can offer.

Whether it's a hand-forged door lock, an elaborate custom entryway, or a complete window & door millwork package, Architectural Traditions has the design and production resources to make it happen.

Their proprietary multi-step prefinish process utilizes an exclusive rubbed-oil finish to enhance the true beauty of each wood species offered: Íncense Cedar, Alder, Wormy Maple, Cherry, Mahogany, Walnut, Mesquite or Spanish Oak.

Perfected over two decades,

Architectural Traditions texturing processes have created an impressive array of authentic distresses to complement any architectural style.

Architectural Traditions' products are available throughout the country to enhance each regional architectural style.



Authorized Dealers Who Sponsored This Ad/Advertorial:

Bakersfield, CA

GH SLACK & SONS 2741 Landco Drive 661-325-5878 Fax: 661-325-2032

Campbell, CA

PACIFIC WOOD WINDOW 1077 Dell Avenue

800-698-4324 Fax: 408-370-4590

Carlsbad, CA

DESIGNLINE WINDOWS AND DOORS

5674 El Camino Real Ste. K 760-931-9422 Fax: 760-931-9465

Indio, CA

J B FINISH

82-750 Atlantic Avenue 760-342-6300 Fax: 760-342-6213

Palm Desert, CA

DESIGNLINE WINDOWS AND DOORS

41-995 Boardwalk, Suite A2 760-207-8189 Fax: 760-931-9465

Redondo Beach, CA

FRAMED OPENINGS 2209 Artesia Boulevard 310-370-3088 Fax: 310-370-4941

Rocklin, CA

CALIFORNIA ARCHITECTURAL TRADITIONS 2591 Warren Drive


916-624-9600 Fax: 916-624-9601

San Diego, CA

THE PELLETIER COMPANY 4028 Wabaska Drive 619-222-1750 Fax: 619-222-1786

Special Advertising Section

QUANTUM



As a leading manufacturer of premier, custom wood windows and doors since 1982, architects and builders have come to rely on Quantum to deliver incomparable value. Each window and door is built to exacting specifications and backed by our 15/5/3 warranty—one of the longest and strongest in the industry. Give us a call to see how well Quantum will fit your next project.

Specified by leading architects since 1982.

QUANTUM WINDOWS & DOORS, INC.

1-800-287-6650 qsales@quantumwindows.com www.quantumwindows.com











QUANTUM Windows & Doors, Inc.

hen architects have specific details in mind, whether a critical match or something new, they think of Quantum Windows & Doors. Since 1982, Quantum has been manufacturing premier, all-wood,



Butler Armsden Architects: Photo: Donna Kempner

custom windows and doors and leading architects across the country know they can turn to Quantum to interpret their specifications flawlessly.

Experienced and dedicated professionals collaborate with you to ensure every detail meets the design objective. From the selection of the wood species to the hardware and glazing options, to the desired in-house applied finishes, Quantum partners with you. Engineering and testing play a significant role in Quantum's quality program and products meet or exceed the highest industry standards.

Choices abound in window and door styles and include the company's incomparable Lift/Slide and Slide/Fold doors. Quantum's adeptness to meet the most demanding



Patano Architects / Build LLC Photo: Art Grice

design criteria is evident in every window and door.

Collaboration starts with a phone call to *Quantum*. 1-800-287-6650.

Quantum is dedicated to offering solutions that bring your vision to life. We don't just take a standard style and make it fit. We build everything to your specification in the wood species of your choice and finished according to your plan.



ane Williams Architects Photo: Michael Jensen



Stone Design Photo: Ira Eichner

It's all in the details.

Dual-sealed insulating glass manufactured in-house Unsurpassed craftsmanship True-divided lites Multi-point locking systems Thermal & structural testing 15/5/3 warranty

QUANTUM WINDOWS & DOORS, INC.

1-800-287-6650 qsales@quantumwindows.com www.quantumwindows.com

GOOD BETTER GRAHAM

REAL-WORLD PROTECTION FOR TODAY'S BUILT ENVIRONMENT

The harsh realities of today's built environment can require very unusual windows. Graham Architectural Products makes windows of uncommon quality for even special applications – for a safer, more pleasant interior environment.

"Good, Better, Graham" means the best windows for your needs.



The primary source of noise intrusion in both homes and buildings is through the

windows. Graham is a leader in the battle against noise pollution in building interiors. Using the right window in educational facilities can mean the difference between performance-enhancing quiet and learning-challenging chaos. Graham's acoustically-rated fenestration products are available in structural aluminum or PVC, in a full spectrum of window styles, STC levels, and operating systems. Sound solutions for commercial, institutional, and residential environments.



Graham has joined The War on Terror with a full line of blast mitigation windows. With

federal agencies mandating windows for public buildings that meet Level II GSA certification test criteria for bomb blast threats, Graham has responded with reinforced blast mitigation products in casement, double-hung, and fixed configurations. Blast mitigation for historical renovation projects are a specialty, thanks to Graham's extensive selection of proprietary architectural design tools.



Graham offers a high-performance, durable alternative to aluminum, PVC, and clad-wood

windows. Pultruded fiberglass is an advanced framing material that expands at the same rate as glass, so that all components work together for superior condensation protection. Graham fiberglass windows are available in casement, double-hung, sliding windows and doors, plus a terrace swing door. Choose them for lower U-values, superior wind-load resistance, and long life, even in challenging chemical or salt air environments.



Architectural • Heavy Commercial

Acoustical Windows
 Sliding Glass Doors

• Terrace Doors • Bomb Blast • Hurricane

800-755-6274

www.grahamwindows.com

Graham Windows

Graham Provides Windows for Two Lake Tahoe Marriott Resort Properties

Lake Tahoe, CA – Graham Architectural Products has replaced the original windows in historic hotels from coast to coast, including San Francisco's Mark Hopkins and Philadelphia's Ritz Carlton properties.

Last year, Graham



Marriott Timber Lodge, Lake Tahoe, CA (Architect: Jung/Brannen Associates, Inc.)

tackled two new-construction Marriott ski resort hotel projects in South Lake Tahoe, California.

Graham manufactured 604 Series 2075 single-hung commercial aluminum windows for Marriott's Timber Lodge. Applied muntins and River Rouge Red Duranar® finish complement the red brick building exterior. Also installed: 18 Graham 0900 Series sliding glass doors. For The Marriot Grand Residence Club, contractor A-1 Glass installed 899 Graham Series 6700 fixed and casement windows, 157 fixed Series 1450 windows, and 158 Series 7000 terrace doors. Preset panning and 1-1/2" internal muntins complemented the red window finish. All windows help protect against outside noise and save energy.

Historic El Segundo High Restored To Former Glory with Graham Thermal Windows

El Segundo, CA – El Segundo High School, located in the Southern California village of the same name, is known for high academic achievement and for its signature Missionstyle bell tower.



its signature Mission- El Segundo High School, El Segundo, CA style bell tower. (Architect: Anshen & Allen)

In 1997, as part of a three-phase \$49 million renovation and new construction program, Graham Architectural Products was selected to replace all the windows in the original brick structure, built in 1927.

Graham subcontractor, Artesia Glass, installed 73 large thermally-improved Series 6700 structural aluminum windows. The new fixed and awning-style low-e glass windows not only outperform the originals, they successfully replicate their true-divided-lite muntins and graceful arch tops. A historically accurate pre-set panning system emulates the appearance of the building's original architecture.

GOOD, BETTER, GRAHAM

means the best windows for your needs.

Since 1972, Graham Architectural Products has been providing building owners and architects with some of the industry's highest-quality commercial windows and glass doors. Whether customers are looking for hurricane-impact resistant, blast mitigation products, or acoustical windows in casement, hung, dual action, sliding, fixed, or projected window style, Graham offers many choices.

The company's sliding glass doors and terrace doors are perfect complements for Graham windows. Graham's current marketing theme, GOOD, BETTER, GRAHAM, conveys the message that architects and owners can always expect the best windows for their needs.

Upscale La Jolla Hi-Rise Retirement Community Wants Only The Best


La Jolla, CA

– The Pacific
Regent is a
21-story luxury retirement highrise offering
the ultimate
in individual
comfort and




(Architect: Simpson Gumpertz & Hager)

convenience, built in 1991.
Last year, when it came time to replace the building's original windows, Graham installed 1,885 Series 6600 heavy commercial aluminum fixed and casement windows. The tinted insulated glazing system is PPG Arctic Blue. Luxurious Graham terrace swing doors with one-inch glazing completed the project.



Your First Source for Fire Rated Glazing





SUPERLITE II-XL IN GPX GLASSPROTEX™

Sunset Elementary, San Ysidro, CA Coup Smith Diaz Architects

SAFTIFIRST

BURNING CALIFORNIA ISSUES – WILDFIRES AND PROTECTING PROPERTY LINES.

How do we protect homes built in fire zones while still affording visibility and daylight? In overpopulated cities with tight property lines, what is the most cost effective way to protect them?



SAFTIFIRST, a California manufacturer, challenged by these issues, developed SuperLite I-XLTM 45/60-minutes, a patented technology that helps stop the spread of fire by reflecting heat back towards the fire source, protecting lives and property from the dangerous transfer of radiant heat.

This low cost solution provides safe egress and fire protection in schools, hospitals, historical renovations, wildfire residential areas,




and around property lines. SuperLite I-XL meets the impact safety rating, CPSC Cat. II 400 ft.lbs. Other features include, clear 1/4" glass with 81% light transmission, survives thermal

shock from sprinklers, listed by Intertek/Warnock Hersey, and manufactured in U.S. for fast lead times.

Authorities having jurisdiction (AHJ) across the nation have approved this non-hose stream tested product because of its enhanced characteristics.

Visit www.safti.com for more information.

Special Advertising Section



Finish *FIRST*In Life Safety

SAFTIFIRST introduces the only safety wired glass Oproduct, SuperLite I-W that meets Category II impact safety-ratings (400 ft.lbs.).

Other recently introduced
wired-replacements
only meet the
lower Category I
and are limited in size.
SuperLite I-W
is a low cost solution
replacing unsafe
wired glass,
protecting against
injury and liability.

Architectural Builders Door Supply

- · European Windows & Doors
- Exotic Woods & Metals
- · Folding · Sliding · Panoramic

Luxurywindows.com

Architectural Builders



indows are to the house, what eyes are to the soul.

Your windows and doors tell a story about your home. What statement do you want to make?

In search of something really special? European windows and doors with an American twist. Add performance and style for the more discerning customer.

Curves, Corners or Straight up? What's your flavor?

Specializing in larger openings for Coastal or Desert Communities

Thermally broken for absolute climate control

The highest performing pocketing door systems for exterior applications. Eliminates water and air



infiltration. Removable wall interlocker provides for easy access if future service is needed.

All Stainless Steel hardware packages provide precision performance and no corrosion.

Invisible flush tracking with hidden drain system. 3 styles to choose from.

From Contemporary to Tuscan, we have a selection of the finest quality window products in the world.

Furnish your project with elegant windows and doors.

Architectural Builders Window&Door Supply



Prefinished Window & Door Solutions



- European Windows & Doors
- Exotic Woods & Metals
- Folding Sliding Panoramic



Stainless Steel • Bronze • Copper • Aluminum • Unlimited Choices of Wood & Finishes

We look forward to seeing you at the showroom

Luxurywindows .com

Luxurywindows .com





"Engineered for Larger Openings"

At Architectural Builders Window & Door Supply Inc. our main goal is to provide you, our customer with the highest quality of doors & windows in the industry. We are able to accommodate your most creative and demanding architectural needs as well as the most basic.

Architectural Builders is pleased to

introduce several lines of European windows and doors. You as the builder, architect or designer will be providing the homeowner with more than just windows and doors. You'll provide them with the opportunity to dress their homes just as they would with fine furniture. "Setting them and you apart from the rest".


Architectural Builders Windows Door Supply

12245 World Trade Dr. #D San Diego CA 92128 Ph: 858-451-1451 Fax: 858-676-1026 Luxurywindows.com

The Largest Selection of Stainless Steel and Bronze Windows, Doors and Curtain Walls







Our motive for creating the ultimate fire barrier is completely transparent, saving lives



Pilkington **Pyrostop**™

The motive behind Pilkington **Pyrostop**[™] Fire-Resistant Glass? To provide critical time for the safe escape of the building occupants and protected access for fire fighters. The Pilkington **Pyrostop**[™] products are made from special laminates of glass and transparent intumescent interlayers that creates an opaque barrier against heat, flames and hot gases. Blocking the radiant heat during a fire is the key to protecting the occupants as well as the rescue teams.

Product Features:

- Perfect product for high activity environments such as schools and gymnasiums.
- · Optical clarity and quality of clear glass, with high light transmission.
- Building codes permit to be used as a glass wall.
- · Passes hose stream tests required in the USA.
- · Various security options available.
- Impact resistant up to Cat II.
- · Cut to your dimensions in Ohio, allowing for short lead times.
- Interior and exterior products available in 45, 60, 90, and 120 minute configurations.
- Can be combined with other Pilkington products to meet your needs.
- · Underwriters Laboratory Inc (UL) approved and listed.

Find out more. Call Technical Glass Products (TGP) at 800-426-0279, fax 800-251-9857 or visit www.fireglass.com today.

Pilkington North America www.pilkington.com/fire






REGISTER TODAY!

Constructing in the 21st Century: New Ways to Think, New Ways to Build

September 28-29, 2005 Millennium Biltmore Hotel Los Angeles

KEYNOTE SPEAKERS:



Timothy J. Leiweke, President & CEO, Anschutz Entertainment Group



Major General Charles E. Williams, Director, Overseas Building Operations, U.S. State Department



Association Partner:



Partners:
Autodesk





Sponsors:



Supporting Sponsors





The industry's leading contractors, engineers, architects, equipment and building product manufacturers, and building and facility owners will gather to discuss trends, innovations and business issues. The Forum's interactive panel discussions include:

- Can the Leaders of an Industry Change the Way Their Business Works?
- Building Information Modeling: Owners, Architects,
 Engineers and Contractors Confront the Future, Today
- The Future Workforce: What Are They Learning? What Should They Be Learning?
- LEED: Green and Environmentally Sensitive and ...
 Worth It?

For a complete list of panelists or to register, visit the Forum website. www.construction.com/TopLeaders.asp/

Call: 212-904-4634 or E-mail: chuck_pinyan@mcgraw-hill.com

Confirmed Panelists include:

Ron Austin, Project Manager, Miami Performing Arts Center Sid Dickerson, Senior Vice President, Hirschfeld Steel Co. Inc. Hank Harris, President and Managing Director, FMI Corp. Ray Landy. President, DMJM H&N

Jim A. Mitchell, V.P. Capital Projects/Risk Management, PCL Constructors Inc.

Frank Musica, Risk Management Attorney, Victor O. Schinnerer & Co. Inc.

Huw W. Roberts, AIA, CSI, Global Marketing Director, Building, Bentley Systems Inc.

Gerry Salontai, CEO, Kleinfelder


Dennis Shelden, CIO, Gehry Technologies

Kevin Wedman, Chief Building Official, California Energy Commission, and Director of Co-Compliance Services, Bureau Veritas, Berryman & Henigar

Rod Wille, Senior Vice President, Manager of Sustainable Construction, Turner Construction Co.



NA.



september 23—25, 2005 all together now

Asilomar Conference Grounds, Pacific Grove, CA For additional information and registration, visit www.aiacc.org

Credits

cover: drawing, Rob Quigley; typography, Bob Aufuldish page 12: illustrations, courtesy of the author page 20: photo, Julius Shulman, used by permission Special Collections Department, Getty Research Institute page 22: drawing, used by permission Gregory Ain Collection Architectural Drawing Collection (ADC), University of California, Santa Barbara

page 24: drawing, used by permission Gregory Ain Collection Architectural Drawing Collection (ADC), University of California, Santa Barbara

page 30-35: photos, drawings, **Daniel Castor** page 36-47: photos, **Richard and Dione Neutra**; drawings, **courtesy of Richard and Dione Neutra archives** page 116: photo, **Lee Manning**

Coda



1414 Fair Oaks Avenue

John Chase, Assoc. AIA

1414 Fair Oaks is a 1958 office building by Smith and Williams in South Pasadena, with landscape design by Garrett Eckbo's firm, Eckbo, Dean and Williams. It is important for three reasons. It incorporates outdoor space as an integral part of its design, it has a design vocabulary of great clarity, and it was once a venue for design collaboration between creative disciplines.

The project is clearly broken into individual buildings and building sections. The height of hyperarticulation is reached where the open wire web trusses supporting the floor of a second-story wing are divorced from the structure of the roof of the one-story section below it. The two floors cross each other as autonomous design elements.

The high vaulted, metal mesh-enclosed space at 1414 Fair Oaks is alternately, and of equal importance, indoor or outdoor space, landscape or office space. In this sense, it reflects the cooperation of the offices it contained. Three discrete suites house the offices of architects Smith and Williams, landscape architects Eckbo, Dean and Williams (forerunner of today's EDAW), and planners Si Eisner and Lyle Stewart. Together they formed the partner-ship called Community Planners. Community Planner's designs "include nearly every classification of

architectural work from a garden tea house to a complete city," according to Whitney Smith.

arcCA Board Member Pierluigi Serraino, Assoc. AIA, writes in his book Modernism Rediscovered, beautifully illustrated by Julius Shulman's photographs, "The setting provided the firms with the opportunity for collaborative projects, while maintaining independent practice." This is an example of cross-disciplinary professional practice that has rarely been equaled since.

Another building was added to the complex at the East end of the site by Smith & Williams, fronting on Fair Oaks, sometime after the main building was completed. It appears boxy and blank, and unshielded by the sun, in contrast to the original building. The creative tenants of the building are long gone, replaced by CPAs and other mainstream office uses. Wood elements are in need of re-staining, and the landscape needs a regime of replanting and restoration.


In a brief high school internship at Smith & Williams in 1969, the chief lesson I learned in this building was that design not only resulted in the creation of physical objects but conversely was also the product of a matrix of action, of use, of social and cultural meaning. The result of Smith & Williams, and Eckbo, Dean & Williams' design process at 1414 Fair Oaks is a building that deserves to be better known as a temple of high modern design.













ENGINEERING SERVICES

- Mechanical
- Electrical
- Plumbing
- Fire Protection/Life Safety
- Telecommunications/IT
- Architectural Lighting Design
- LEED® Sustainable **Engineering Design**

SAN FRANCISCO 405 Howard Street, Suite 500 San Francisco, CA 94105 415.398.3833

475 Fifth Avenue New York, NY 10017 212.532.9600

SEATTLE 1417 Fourth Avenue, Suite 400 Seattle, WA 98101 206.342.9900

www.flackandkurtz.com



For any application enjoy the same great benefits

- · Ultra quiet movement (44dbA at three feet)
- · Digital precision alignment of multiple shades
- · Seamless integration with lighting control systems

Visit www.lutron.com/shadingsolutions or call 1.877.258.8766 ext. 561 to learn more about Sivoia QED | roller 64.

